

SURVEY & REMONUMENTATION

DEC 15 1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
REMONUMENTATION

RECORDED

93 DEC -6 AM 10:58

REGISTER OF DEEDS

Shiawassee County, Mich.

for corners in

Shiawassee (County)	Located In:	Corner Code ##
Public Land Survey	T 5N R 2E	K-13
	T R	
	T R	
	T R	
Property Controlling in Section	S T R	
	S T R	
Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
 Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Norman C. Caldwell, in a field survey on November, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-13 Sec. cor., 35 & 36, T5N-R2E
 Wood post placed by J. Wampler, 1826 Survey by O. M. Elliot, January 1967
 N36 1/2°W 32 lks. (21.12') 8" Ash C.R.-41, pg. 68
 N58 1/2°E 14 lks. (9.24') 23" Maple Indicates fnd. corner
 No monument or refs. given
 Survey by O. M. Elliot, date unknown, C.R.-38, pg. 51
 Monument not given

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-13 Sec. cor., 35 & 36, T5N-R2E
 Measured 33' South from old fence post for temporary position. Dug a 10' x 12' hole 3' deep (1± below original soil), Fnd. no evidence of monument. Position established by using local collateral evidence and agrees well with occupation, closing corner, 1/16 & 1/4 corner relationships. Set a standard 20" Harrison marker as approved by Shiawassee County Peer Review Group and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13 Sec. cor., 35 & 36, T5N-R2E
 Set a standard 20" Harrison marker as approved by Shiawassee County Peer Review Group and is accepted as the best available evidence of the position of the original corner.
 N60°W 31.88' Chis. "+" top center N. end 15" CMP
 S65°W 33.80' Chis. "+" top center S. end 15" CMP
 S15°E 35.48' Set N & T #12018 E. fc 5" Elm
 S60°E 47.27' Set N & T #12018 N. fc 14" Oak
 N86°E 99.0' Fnd. 1/2" iron pipe @ NW Cor. Sec. 1, T4N-R2E
 N86°E 95.7' Fnd. grader blade



Signed by *Norman C. Caldwell* Date 20 NOV 93
 Surveyor's Michigan License No. 12018