

**SURVEY &  
REMONUMENTATION**

DEC 15 1993

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
REMONUMENTATION**

RECORDED

93 DEC -6 AM 10:58

REGISTER OF DEEDS  
*[Signature]*  
SHIAWASSEE COUNTY, MICH.

Register of Deeds Stamp & File Number

For corners in \_\_\_\_\_  
Shiawassee (County) Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

Public Land Survey	T	5N	R	2E	L-13
	T		R		
	T		R		
	T		R		
Property Controlling in Section	S		T	R	
	S		T	R	
Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Norman C. Caldwell, in a field survey on November, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

L-13 S 1/4 cor., Sec. 36, T5N-R2E  
Wood post placed by J. Wampler, 1826  
N86°W 16 lks. (10.56') 8" Sugar  
N72°E 19 lks. (12.54') 7" Sugar  
No subsequent record

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13 S 1/4 cor., Sec. 36, T5N-R2E  
Set a temporary position using local collateral evidence. Dug a 15' x 15' x 3' deep hole. Fnd. a pointed stone and it agrees well with occupation 1/16 & Sec. cor., relationships. Set a standard 20" Harrison marker at this position as approved by Shiawassee County Peer Review Group and is accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13 S 1/4 cor., Sec. 36, T5N-R2E  
Fnd. pointed stone, replaced with a standard 20" Harrison marker at this position as approved by Shiawassee County Peer Review Group and is accepted as a careful and faithful perpetuation of the position of the original corner.  
N80°W 152.90' Set p.k. & tag #12018 S. fc wood post  
S65°E 90.12' Set p.k. & tag #12018 N. fc wood fnc post  
S50°E 43.92' Set N & T #12018 NE fc 4" Elm  
S55°W 51.50' Set N & T #12018 NW fc 4" Elm



Signed by *[Signature]* Date 20 NOV 93  
Surveyor's Michigan License No. 12018