

**SURVEY &
REMONUMENTATION**

MAY 28 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**
Shiawassee
(County)

Located in: _____ Corner Code # _____

RECORDED
96 NOV 18 PM 3:39

REGISTER OF DEEDS
Kay S. ...
SHIAWASSEE COUNTY, MICH.

1. Public Land Survey T 5N R 2E M-10
T _____ R _____
T _____ R _____
T _____ R _____
2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Mark L. VanRaemdonk, in a field survey on July 30, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the current points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Original: Joseph Wampler, D.S., 1826.
Monument: Wood post
Accessories: Beech 18 S18°W 9
do 7 N43°E 18
- E.S. Brewer, L.C.R.C. recorded Liber 2, page 196, 9/6/79.
Monument: Found 1" square iron rod about 3' West of centerline of Cork Road, graveled.
Accessories: 3" iron anch. fence post East 27.3'
35" Ash N20°E 89.5'
39" Maple S20°E 105.1'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" pipe at location referenced in no. 2 above. Excavated for Harrison Marker and found 1" square iron rod lying down. The square rod was tapered to a point and about 12" long. I have found similar irons that have been referred to as "drag teeth" by E.F. Joslin in County Surveyor records. Accepted this location as the careful and faithful perpetuation of the original corner position. Found no conflicting evidence.

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

Replaced 1/2" pipe with standard Shiawassee County Harrison Marker monument. The monument was stamped "REMON 24622" and is witnessed by the following accessories:

- S80°E 24.77' Fnd. N&T #25832 in N. face 8" Maple
- S85°W 32.83' Set N&T #24622 in N. face util. pole
- N30°E 43.27' Set N&T #24622 in SE face 5" Maple
- N10°W 96.00' Set N&T #24622 in E. face 10" Maple



Signed by Mark L. VanRaemdonk
Surveyor's Michigan License No. 24622

Date Nov. 12, 1996

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS JAN 18, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

APPROVED
7/8/96 MLU
County Remonumentation
Peer Review Group

LIBER 1R **PG** 180