

**SURVEY & REMONUMENTATION**

DEC 15 1993

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**REMONUMENTATION**

RECORDED

93 DEC -6 AM 10:58

REGISTER OF DEEDS

*Angela...*  
 SHIawassee COUNTY, MICH.

Register of Deeds Stamp & File Number

For corners in

Shiawassee (County)	Located In:	Corner Code -#
Public Land Survey	T 5N R 2E	M-11
	T R	
	T R	
	T R	
Property Controlling in Section	S T R	
	S T R	
Miscellaneous Property in Sec.	S T R	
	S T R	

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 Private Claims \_\_\_\_\_

Norman C. Caldwell, in a field survey on November, 19 93, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Description of original monument and accessories and/or subsequent restoration:

M-11 Sec. cor., 25 & 36, T5N-R2E & Sec. 30 & 31, T5N-R3E

Wood post placed by J. Wampler, 1826  
 S31°W 6 lks. (3.96') 5" Birch  
 N21°W 21 lks. (13.86') 6" Birch

Survey by E. F. Joslin, Co. Surveyor, Feb. 1900, recorded in Book E, pgs. 246 & 247, S.C.R.  
 1" iron pipe at corner  
 S53 1/4°E 59.5 lks. (39.27') 6" Maple  
 S21 3/4°E 95.75 lks. (63.20') 12" B. Walnut

Unrecorded survey by R. L. Mitchell, 1976  
 Fnd. 1 1/4" pipe  
 N45°W 36.05' Road sign  
 N45°E 41.15' N & F in Tele. pole  
 S45°E 39.15' N & F in 20" Maple

L.C.R.C. by E. S. Brewer, August 1978 recorded in Corners L. 2, pg. 196  
 Fnd. 1 1/4" pipe set by others in 1976  
 N45°W 35.9' Road sign  
 N45°E 41.15' Nail in Tele. pole  
 S45°E 39.1' Nail in 24" Maple

Unrecorded survey by A. F. Miller, 1979  
 Fnd. 1 1/4" pipe  
 N45°W 36.05' Road sign  
 N45°E 41.15' Tele. Pole  
 S45°E 39.15' N & F 20" Maple

Survey by M. L. Vanraemdonck, 1984 recorded in Surveys L. 4, pg. 172  
 Fnd. 1 1/4" pipe  
 N45°W 35.90' Road sign  
 N45°E 41.15' Tele. Pole  
 S45°E 39.10' 24" Maple  
 South 4' CL Braden Road

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

-11 Sec. cor., 25 & 36, T5N-R2E & Sec. 30 & 31, T5N-R3E

Fnd. 1 1/4" pipe per Co. Surveyor's records, L. 2, pg. 196 of Corners, L. 4, pg. 172 of Surveys and other records. Replaced with standard 20" Harrison marker as approved by Shiawassee County Peer Review Group and is accepted as the best available evidence of the position of the original corner.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

-11 Sec. cor., 25 & 36, T5N-R2E & Sec. 30 & 31, T5N-R3E

Fnd. 1 1/4" pipe per Co. Surveyor's records, L. 2, pg. 196 of Corners, L. 4, pg. 172 of Surveys and other records. Replaced with standard 20" Harrison marker as approved by Shiawassee County Peer Review Group and is accepted as the best available evidence of the position of the original corner.  
 S45°E 39.67' Set N & T #12018 NE fc 24" Maple (R-tree)  
 N45°E 41.10' Fnd p.k. in Tele. Pole  
 N10°W 71.78' Chis. "+" top center W. end 18" CMP culvert  
 N20°E 73.45' Chis. "+" top center E. end 18" CMP culvert



signed by *Norman C. Caldwell*

Date 20 NOV 93

Surveyor's Michigan License No. 12018