

**SURVEY &  
REMONUMENTATION**

DEC 15 1993

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970  
REMONUMENTATION

RECORDED

93 DEC -6 AM 10:58

REGISTER OF DEEDS

*[Signature]*  
SHIawassee COUNTY, MICH.

For corners in

Shiawassee (County)	Located In:	Corner Code-#
1. Public Land Survey	T 5N R 3E	L-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman C. Caldwell, in a field survey on November, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

L-11 1/4 cor., Sec. 25 & 36, T5N-R3E

Wood post placed by J. Mullett, 1823,  
N54°E 23 lks. (15.18') 6" Elm  
S45°W 14 lks. (9.24') 5" Tamarack

Surveys by M. P. Pike, Oct. 1973  
July 1974 recorded in surveys L. 1,  
pg. 537 & L. 2, pg. 20  
Fnd. cor., (mon. & refs. not given)

Survey by E. S. Brewer, Nov. 1980  
recorded in Corners. L. 2, pg. 229  
and Surveys L. 3, pg. 453  
Fnd 1/2" rerod 5' N. of Cl. gravel rd.  
S2 1/4°W 29' Old 12" Anchor post  
N02°W 30' Old 12" Anchor post  
N40°E 32.5' Pin, old 36" Elm stump  
N62 1/4°E 56' Cent. 12' Spruce tree

Survey by M. L. Vanraemdonck, Oct. 1986/  
Oct. 1990 recorded in Surveys, L. 4, pgs. 540 &  
541 & L. 5, pg. 927  
Fnd. 1/2" rerod  
N80°E 59.73' W. face steel mailbox post  
N50°E 61.55' PK W. face 10" Cedar  
South 32.5' Rerod w/cap #12024  
North 29.65' SE cor. R.R. tie fence post

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


L-11 1/4 cor., Sec. 25 & 35, T5N-R3E

Fnd. 1/2" rerod per corners L. 2, pg. 229 & Surveys L. 1, pg. 537,  
L. 3, pg. 453, L. 4, pgs. 540 & 541 & L. 5, pg. 927. Replaced  
with standard 20" Harrison marker as approved by Shiawassee County  
Peer Review Group and is accepted as the best available evidence  
of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-11 1/4 cor., Sec. 25 & 35, T5N-R3E

Fnd. 1/2" rerod per corners L. 2, pg. 229 & Surveys L. 1, pg. 537,  
L. 3, pg. 453, L. 4, pgs. 540 & 541 & L. 5, pg. 927. Replaced  
with standard 20" Harrison marker as approved by Shiawassee County  
Peer Review Group and is accepted as the best available evidence  
of the position of the original corner.  
N65°E 56.20' Set PK NW face 12" Spruce (R)  
North 29.65' SE cor. R.R. tie anchor post (R)  
N80°E 59.66' W. face steel mailbox post (R)  
South 32.49' Fnd. rerod w/cap #12024 (R)



Signed by *[Signature]* Date 20 NOV 93  
Surveyor's Michigan License No. 12018