

**SURVEY & REMONUMENTATION**

DEC 15 1993

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970  
REMONUMENTATION

RECORDED

DEC -6 AM 10:58

For corners in

Shiawassee (County)	Located In:	Corner Code #
1. Public Land Survey	T 5N R 3E	L-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

REGISTER OF DEEDS  
*John Smith*  
SHIAWASSEE COUNTY, MICH.

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman C. Caldwell, in a field survey on November, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

L-13 S 1/4 cor., Sec. 36, T5N-R3E

Wood post placed by J. Mullett, 1823  
N34°E 53 lks. (34.98') 4" Tamarack  
N39°W 35 lks. (23.10') 6" Tamarack

Survey by E. F. Joslin, Co. Surveyor (no date), Book A. pg. 90, mon. not given  
S16 1/2°E 32 lks. (21.12') 8" Tamarack  
S25 1/2°W 38 lks. (25.08') 7" Tamarack

Surveys by G. R. Boss, Oct. 1977, recorded in Surveys L. 2, pg. 593 - 596, surveys show a calculated position, midway b/w K-12 & M-12 showing a slight deflection at this corner.

Survey by D. D. Hughes, Dec. 1980, recorded in Surveys L. 3, pg.s 468 - 471, Fnd. 1/2" iron rod at rec. dist. shown on Boss' surveys

S'ly 30.03' Fnd. Nail N/S 10" Poplar  
S45°W 37.19' Fnd. boat spike N/S 30" Oak  
W'ly 60.65' Fnd. 1/2" iron rod at N 1/4 cor., Sec. 1, T4N-R3E

Survey by D.D. Hughes, March 1991, recorded in Surveys L. 5, pgs. 904 & 905 & 933 & 934

Fnd. 1/2" iron rod  
South 30.03' Fnd. Nail N/S 10" Poplar  
North 33.04' Fnd. 1/2" iron  
S45°W 37.19' Fnd. boat spike N/S 30" Oak  
West 60.65' Fnd. 1/2" iron rod for N 1/4 cor., Sec. 1, T4N-R3E

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

L-13 S 1/4 cor., Sec. 36, T5N-R3E

Fnd. 1/2" iron rod per recorded surveys L. 2, pgs. 593 - 596, L. 3, pgs. 468 - 471, & L. 5, pgs. 904, 905, 933 & 934. Replaced with a standard 20" Harrison marker as approved by the Shiawassee County Peer Review Group and is accepted as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

L-13 S 1/4 cor., Sec. 36, T5N-R3E

Fnd. 1/2" iron rod per recorded surveys L. 2, pgs. 593 - 596, L. 3, pgs. 468 - 471, & L. 5, pgs. 904, 905, 933 & 934. Replaced with a standard 20" Harrison marker as approved by the Shiawassee County Peer Review Group and is accepted as the best available evidence of the position of the original corner.  
S45°W 37.02' Fnd. Nail & "Boss Eng." tag E. face 30" Oak (R)  
West 60.75' Fnd. 1/2" rered for N 1/4 cor., Sec. 1, T4N-R3E (R)  
N25°W 31.18' Set Nail & Tag #12018 in W. face 12" Elm  
N75°W 42.36' Set Nail & Tag #12018 in NE face 6" Ash



Signed by *Norman C. Caldwell*  
Surveyor's Michigan License No. 12018

Date 20 NOV 93