

**SURVEY & REMONUMENTATION**

MAY 28 1997

COMMISSION

**REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

96 AUG 16 PM 2:36

REGISTER OF DEEDS

*Lyne Smith*  
SHIAWASSEE COUNTY, MICH.

For corners in	Located In:	Corner Code #
Shiawassee (County)		
1. Public Land Survey	T 5N R 4E	L-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Norman C. Caldwell, in a field survey on April 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

L-9 1/4 Corner Common to 24 & 25, T5N-R4E, Burns TWP.

Wood post placed by J.D. Mullett, 1823, S 44 E 12 lks (7.92') 24" Maple, S 87 W 30 lks (19.80') 10" B. Ash. No subsequent surveys.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-9 1/4 Corner Common to 24 & 25, T5N-R4E, Burns TWP.

An extensive search of this area indicates no evidence of the original corner or subsequent restoration.

Examination of the original field notes and topographic features indicates the original surveyors likely did not cross to the east side of the Shiawassee River or continue east to the range line. There are two high sand ridges and three swamps which are not shown in the notes.

This position is determined by prorating the government dimension from the N.W. corner to the river banks and extrapolation beyond to the 1/4 corner. The latitudinal position is determined by existing ancient fences in the area.

This position has been reviewed and accepted by the Shiawassee County Remon. peer group on March 1996.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-9 1/4 Corner Common to 24 & 25, T5N-R4E, Burns TWP.

Placed standard Harrison monument in swamp with steel fence post alongside.

References:

S 45 W 24.80' Center of 2 1/2" pipe  
N 60 W 23.93' 12018 tag in 28" Ash  
N 45 E 3.90' 12018 tag in 5" Ash  
S 85 E 29.00' 12018 tag in 14" Maple  
West 1.00' Steel fence post

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



Signed by *Norman C. Caldwell* Date 21 MAY 1996  
Surveyor's Michigan License No. 12018

**APPROVED**  
3/19/94 MLV  
County Remonumentation  
Peer Review Group

**LIBER IR PG 140**

APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1993  
ADAPTED FOR WORD PROCESSING MARCH, 1993