

SURVEY & REMONUMENTATION

AUG 05 1996

COMMISSION LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

93 DEC -6 AM 10:50

or corners in _____
 Shiawassee _____ (County)
 Located In: _____
 REMONUMENTATION Corner Code ## _____

Public Land Survey	T 5N	R 4E	L-11
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
Property Controlling	S _____	T _____	R _____
In Section	S _____	T _____	R _____
Miscellaneous	S _____	T _____	R _____
Property in Sec.	S _____	T _____	R _____

REGISTER OF DEEDS
Shirley J. ...
 SHIawassee COUNTY, MICH.

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
 Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2								
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Norman C. Caldwell, in a field survey on November, 1993,
 hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
 in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as
 expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
 on this certificate.

Description of original monument and accessories and/or subsequent restoration:

-11 1/4 cor., Sec. 25 & 36, T5N-R4E

Wood post placed by J. D. Mullett, 1848
 N54°E 33 lks. (21.78') 12" B. Oak
 S82°W 52 lks. (34.32') 8" Elm

Survey by E. F. Joslin, Co. Surveyor, 1898
 Fnd. Huggins Corner
 S9 1/2°E 39 lks. (25.74') 6" Maple

Survey by E. J. McCombs, (C.P. Co.), April 1973
 recorded in Surveys L. 1, pg. 484
 Set 1/2" rebar
 N85°W 44.0' SE'ly cor. N bridge abutment
 S85°W 43.32' NE'ly cor. S bridge abutment
 N75°E 89.8' PK Nail tele. riser pole
 N75°W 45.82' PK Nail 8" Walnut

L.C.R.C. by M.D. Pike, May 1973, recorded in Corners
 L. 1, pg. 109,
 Fnd. R.R. Spike
 N80°W 45.83' 12" Oak
 N70°E 89.78' Power Pole

10/07/93

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

-11 1/4 cor., Sec. 25 & 36, T5N-R4E

Corner has been destroyed by placement of 96" CMP
 in road. Reestablished corner position
 by using the NE & NW (R.R. Spike) corners of Sec. 36 as
 used by McCombs Survey (C.P. Co.) per L. 1, pg. 484,
 Set a standard 20" Harrison marker as approved by the
 Shiawassee County Peer Review Group, and is accepted as
 a careful and faithful determination of the position
 of the original corner.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

-11 1/4 cor., Sec. 25 & 36, T5N-R4E

Corner has been destroyed by placement of 96" CMP
 in road. Reestablished corner position
 by using the NE & NW (R.R. Spike) corners of Sec. 36 as
 used by McCombs Survey (C.P. Co.) per L. 1, pg. 484,
 Set a standard 20" Harrison marker as approved by the
 Shiawassee County Peer Review Group, and is accepted as
 a careful and faithful determination of the position
 of the original corner.
 N80°E 89.53' Fnd. PK & Washer NNW face tele. pole (R)
 S65°E 69.98' Set N & T #12018 in North face 8" Elm
 N58°W 63.91' Chis. "+" top center 96" CMP
 S10°E 26.04' Chis. "+" top center 96" CMP



Signed by Norman C. Caldwell Date 20 NOV 93
 Surveyor's Michigan License No. 12018

INDEX

DC

5