

**SURVEY & REMONUMENTATION**

AUG 05 1996

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**REMONUMENTATION**

RECORDED

99 DEC -6 AM 10:58

REGISTER OF DEEDS

*Shirley J. ...*  
 SHIawassee COUNTY, MICH.

Register of Deeds Stamp & File Number

for corners in	Located In:	Corner Code ##
Shiawassee (County)		
Public Land Survey	T 5N R 4E	L-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling	S _____ T _____ R _____	_____
In Section	S _____ T _____ R _____	_____
Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Norman C. Caldwell, in a field survey on November, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

-13 S 1/4 cor., Sec. 36, T5N-R4E  
 Wood post placed by J. D. Mullett, 1848 Survey by E. E. Anderson, 1976, recorded in Surveys L. 2, pgs. 331 & 332  
 N67°E 60 lks. (39.60') 9" W. Oak Fnd. 1/2" rerod  
 N57°W 23 lks. (15.18') 18" B. Oak North 23.19' Spike in fence cor. post  
 Survey by E. J. McCombs (C.P. Co.), 1973 recorded in Surveys L. 1, pg. 484, S75°W 71.90' Nail 14" Hickory  
 Set 1/2" rebar and scattered tile on N05°W 23.35' Tag in 30" Oak  
 line with fence to North & near CL of gravel road.  
 N05°W 23.38' Nail 24" Oak  
 N70°W 78.28' Nail 10" Oak  
 S35°W 24.78' Nail in Power Pole

10/07/93

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

-13 S 1/4 cor., Sec. 36, T5N-R4E  
 Fnd. 1/2" rerod per L. 1, pg. 484 of Surveys, and L. 2, pgs. 331 & 332 of Surveys, replaced with a standard 20" Harrison marker as approved by the Shiawassee County Peer Review Group and is accepted as the best available evidence of the position of the original corner.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

-13 S 1/4 cor., Sec. 36, T5N-R4E  
 Fnd. 1/2" rerod per L. 1, pg. 484 of Surveys, and L. 2, pgs. 331 & 332 of Surveys, replaced with a standard 20" Harrison marker as approved by the Shiawassee County Peer Review Group and is accepted as the best available evidence of the position of the original corner.  
 N10°W 23.04' Fnd. spike w/tag #32332 E. face 34" Oak (R)  
 N05°E 22.83' Set spike w/tag #12018 W. face fence post (R-post)  
 S20°W 24.94' Fnd. spike w/tag #32332 E. face 6" Hickory (R)  
 West 22.00' Fnd. 1/2" rebar at N 1/4, Sec. 1, T4N-R4E  
 S51°W 55.83' Set spike w/tag #12018 N. face Power Pole



Signed by *Norman C. Caldwell* Date 20 NOV 93  
 Surveyor's Michigan License No. 12018