

**SURVEY & REMONUMENTATION**

MAY 28 1997  
COMMISSION

**REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED  
96 AUG 16 PM 2:36

REGISTER OF DEEDS  
*Loye Anstha*  
SHIAWASSEE COUNTY, MICH.

For corners in Shiawassee (County) Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

1. Public Land Survey T 5N R 4E M-9  
T \_\_\_\_\_  
T \_\_\_\_\_  
T \_\_\_\_\_

2. Property Controlling S T R \_\_\_\_\_  
in Section S T R \_\_\_\_\_

3. Miscellaneous S T R \_\_\_\_\_  
Property in Sec. S T R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman C. Caldwell, in a field survey on April 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-9 Standard Corner of Sections 24 & 25, T5N-R4E, Burns TWP.

Wood post placed by J. Mullett, 1823, S 36 W 8 lks (5.28') 3" Tamarack, N 48 W 20 lks (13.20') 5" Tamarack.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-9 Standard Corner of Sections 24 & 25, T5N-R4E, Burns TWP.

There is no apparent record of recovery or restoration of this position. An unrecorded survey by Gilbert G. Bonno, P.S. #32332, dated 28 January 1994, used a 4" steel fence post for alignment of the county line while performing a survey north of Silver Lake Road in Genesee County. We also held this pipe for alignment.

Retracement of an unrecorded survey of section 30, T5N-R4E, and ancient fence lines, indicates a reliable latitudinal position for the closing corner of 19 & 30 which agrees with the government "Jog" to the standard corner of 24 & 25 as determined by this contractor.

This position has been reviewed and accepted by the Shiawassee County Remon. peer group on 19 March 1996

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-9 Standard Corner of Sections 24 & 25, T5N-R4E, Burns TWP.

Placed 8' of 1 1/4" pipe, 6' in ground, top flush with water, on county line.

North 30.93' 4" pipe in 12" conc. base  
South 30.00' Harrison monument  
S 45 E 30.00' Wood fence post (East)  
East 331.30' 60d spike (Trav. point)



Signed by *Norman C. Caldwell* Date 21 MAY 1996  
Surveyor's Michigan License No. 12018

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983  
ADAPTED FOR WORD PROCESSING MARCH, 1993

**LIBER** LR PG 141 **APPROVED**  
3/19/96 M.L.V.  
County Remonumentation  
Peer Review Group