

SURVEY & REMONUMENTATION

AUG 05 1996

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
REMONUMENTATION

RECORDED

93 DEC -6 AM 10:57

For corners in

Shiawassee (County)	Located in:	Corner Code #
1. Public Land Survey	T 5N R 4E	M-11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REGISTER OF DEEDS
[Signature]
 SHIawassee COUNTY, MICH.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Norman C. Caldwell, in a field survey on November, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-11 Sec. cor., 25 & 36, T5N-R4E

Wood post placed by J. D. Nullett, 1848
 N43°E 63 lks. (41.58') 20" W. Oak
 S21°E 72 lks. (47.52') 16" W. Oak

Survey by E. J. McCombs (C.P. Co.), 1973
 recorded in Surveys L. 1, pg. 484,
 Fnd. large stone & tile & wire, laid R.R. spike
 along side for magnetic pull on line with fence
 to North
 N80°W 30.65' Spike 16" Apple
 S45°W 35.75' Rd. sign (Co. line & Braden)
 S45°E 49.0' (Sheridan & Lillie)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-11 Sec. cor., 25 & 36, T5N-R4E

Fnd. large stone, R.R. Spike and Coke bottle per Survey L. 1, pg. 484, replaced with a standard 20" Harrison marker as approved by the Shiawassee County Peer Review Group and is accepted as the best available evidence of the position of the original corner.


10/07/93

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-11 Sec. cor., 25 & 36, T5N-R4E

Fnd. large stone, R.R. Spike and Coke bottle per Survey L. 1, pg. 484, replaced with a standard 20" Harrison marker as approved by the Shiawassee County Peer Review Group and is accepted as the best available evidence of the position of the original corner.

North 4.81' Fnd. boatspike
 North 37.82' Fnd. rod w/cap #10057
 N80°E 97.89' Fnd. "Boss" tag and spike S. face 14" Pine
 S70°E 95.92' Fnd. "Boss" tag and spike N. face Oak



Signed by *Norman C. Caldwell* Date 20 NOV 93
 Surveyor's Michigan License No. 12018