

MAY 28 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Form with fields for Shiawassee (County), Located in: T 6N R 1E, Corner Code # D-4, and numbered sections 1-5 for Public Land Survey, Property Controlling, Miscellaneous, Lot No., and Private Claims.

RECORDED

96 NOV 18 PM 3:38

REGISTER OF DEEDS

Signature of Kaye Shuster and SHIAWASSEE COUNTY, MICH.

Grid table with columns A-L and rows 2-13, showing a location marked at the intersection of D and 8.

I, Mark L. VanRaemdonck, in a field survey on October 22, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the current points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Closing West 1/4 corner Section 8, T6N-R1E

This position was not established in the original government survey. Found no record of establishment of this position by the County Surveyor.

- 1.) David T. Rowe, survey recorded Liber 2, page 182, 6/18/75. Monument: Found conc. nail & bottle cap in centerline pavement. Accessories: East 32.93' 1/2" iron pipe S70°E 35.97' P.K. & disc in W. face 20" Oak

- 2.) Jan S. Fokens, L.C.R.C. recorded Liber 2, page 98, 1/31/78. Monument: Found conc. nail & cap. Accessories: East 32.93' 1/2" iron pipe S70°E 35.97' P.K. & tag in 20" Oak N40°W 65.44' P.K. & tag in 12" Hickory

- 3.) Ronnie M. Lester, survey recorded Liber 3, page 341, 10/18/79. Monument: Refers to L.C.R.C. recorded Liber 2, page 98. Accessories: N&T #18998 in NW side 28" Oak N15°E 117.46' N&T #18998 in SW side 24" Oak S50°E 36.81' N&T #18998 in NE side 10" Poplar S20°E 40.62' N&T #18998 in E. side 10" twin Oak S30°W 98.01'

- 4.) Mark L. VanRaemdonck, survey recorded Liber 6, page 559, 6/25/93. Monument: Found nail & tag. Accessories: East 33.18' 1" pipe S65°E 35.88' N&T W. face 20" Oak S35°E 40.70' N&T E. face 12" Cottonwood S20°E 51.48' S. end 12" conc. culv.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Located concrete nail as referenced in no. 1 through no. 4 above. The origin of this location is unknown. Measurements to corners D-3 and D-5 show that this location was not established using proper procedures. I re-established this location on the Michigan Meridian equidistant from corners D-3 and D-5. This location is 7.7 feet North and 2.7 feet West of the concrete nail. Excavation for Harrison Marker provided no further evidence. Accepted this location as the proper establishment of the corner location.

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

Installed a standard Shiawassee County Harrison Marker monument at the location described above. The monument is stamped "REMON 24622" and is witnessed by the following accessories:

- S20°W 91.51' Set N&T #24622 E. face 16" Cherry
S40°E 54.03' Set N&T #24622 W. face 30" Oak
S55°E 42.95' Set N&T #24622 N. face 30" Oak
N30°E 45.64' Top cen. S. end 12" conc. culv.

Signed by Mark L. VanRaemdonck

Date Nov. 12, 1996

Surveyor's Michigan License No. 24622



APPROVED

County Remonumentation Peer Review Group

APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS JAN 18, 1971 REVISED MAY 14, 1975 REVISED JAN., 1983