

SURVEY & REMONUMENTATION

MAY 28 1997

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

<u>Shiawassee</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>1E</u>	<u>D-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECORDED

96 NOV 18 PM 3:38

REGISTER OF DEEDS

Haye Shubert
 SHIAWASSEE COUNTY, MICH.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

MICHIGAN MERIDIAN

I, Mark L. VanRaemdonck, in a field survey on October 22, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the current points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Closing corner common to Sections 8 and 17, T6N-R1E

- 1.) Original: Joseph Wampler, D.S., 1826.
 Monument: Wood post
 Accessories: R. Oak 32 S1 1/2°E 19 lks.
 Elm 11 N38°E 25 lks.
- 2.) John D. Matonich, Jr., survey recorded Liber 4, page 342, 10/24/85.
 Monument: Found R.R. spike under asphalt pavement
 Accessories: N20°E 62.76' Spike in SE face 14" Poplar
 S25°W 34.28' Chiseled "x" in top conc. headwall
 East 28.31' Spike in S. face 6" Hickory
 West 8.75' W. edge pavement
 East 1.30' Physical centerline Meridian Road
- 3.) John D. Matonich, Jr., L.C.R.C. Liber 2, page 443, 8/25/86.
 Monument: Found R.R. spike under asphalt
 Accessories: Same as no. 2 above.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found railroad spike as referenced in no. 2 and no. 3 above. Found no conflicting evidence. Accepted this location as the original corner position based on the best available evidence. A fence line runs East from this location. I established an amended corner location on the Meridian 1.25 feet West of this location between corners M-4 and M-5, T6N-R1W. Excavation for Harrison Marker provided no evidence. Found no conflicting evidence.

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

Installed a standard Shiawassee County Harrison Marker monument at the amended corner position as described above. The monument is stamped "REMON 24622" and is witnessed by the following accessories:

- S50°W 47.24' Set N&T #24622 in N. face 6" Elm
- S70°E 46.86' Set N&T #24622 in N. face twin 12" Elm
- East 31.24' Set N&T #24622 in N. face 20" Hickory
- N20°E 63.41' Set N&T #24622 in W. face 24" Poplar



Signed by *Mark L. VanRaemdonck*

Date Nov. 12, 1996

Surveyor's Michigan License No. 24622

APPROVED

11/13/96 MLV
 County Remonumentation
 Peer Review Group

APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS JAN 18, 1971
 REVISED MAY 14, 1977
 REVISED JAN., 1988

LIBER 1 D PG 117