

MAY 28 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

RECORDED

96 NOV 18 PM 3:38

REGISTER OF DEEDS

Kaye Smith
SHIawassee COUNTY, MICH.

Shiawassee (County) Located in: Corner Code #

1. Public Land Survey T 6N R 1E D-6
T R
T R
T R

2. Property Controlling S T R
in Section S T R

3. Miscellaneous S T R
Property in Sec. S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

MICHIGAN MERIDIAN

I, Mark L. VanRaemdonck, in a field survey on October 10, 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the current points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
Closing West 1/4 corner Section 17, T6N-R1E

This position was not established in the original government survey. Found no record of establishment of this position by County Surveyor.

1.) Douglas K. Richardson, L.C.R.C. recorded Liber 2, page 886
Monument: Found railroad spike in Monument Box in the centerline of Parker Road, 4' West of the centerline Meridian Road.
Accessories: Nail & ribbon E. side Power Pole N10°W 83.65'
Nail & ribbon NE side Power Pole S40°E 47.57'
Nail and ribbon E. side 24" Walnut S10°W 79.48'
Nail and ribbon NW side 20" wide Maple N40°E 73.33'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found railroad spike in Monument Box as referenced in no. 1 above. This location is 2.2 feet South of being equidistant from corners D-5 and D and is 6.05 feet West of the Michigan Meridian. I accepted this location for its position North and South but established a position on the Michigan Meridian between corners M-5 and M-6, T6N-R1W, 6.05 feet East of the railroad spike. Found no conflicting evidence.

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

Installed a standard Shiawassee County Harrison Marker monument at the position described above. The monument is stamped "REMON 24622" and is witnessed by the following accessories:

- N40°E 68.93' Set N&T #24622 in S. face 24" Maple
- S45°E 43.54' Set N&T in NE face util. pole
- N20°W 85.24' Set N&T in E. face util. pole
- S25°W 81.12' Set N&T in E. face 24" Walnut
- West 6.05' R.R. spike in Monument Box



Signed by *Mark L. VanRaemdonck*

Date Nov. 12, 1996

Surveyor's Michigan License No. 24622

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS JAN 18, 1988
REVISED MAY 14, 1991
REVISED JAN., 1996

APPROVED
11/13/96 MLV
County Remonumentation
Peer Review Group