

1997 **SHIWAASSEE COUNTY**

NOV 10 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Shiawassee</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>1E</u>	<u>K-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____	Recorded Plat _____	
5. Private Claims _____		

RECORDED
97 NOV -6 PM 2:37
REGISTER OF DEEDS
Paul Shubbs
SHIWAASSEE COUNTY, MICH.

Register of Deeds Stamp & File Number

I, Mark L. VanRaemdonck, in a filed survey on June 11-13, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Original: Joseph Wampler, DS 3/27/1826
Mon: Wood Post
Access: Aspen 7 N35°W 504
- Larry Bryan, D. S. 25832, L. C. R. C. Rec. Liber 2, Page 480 1/13/1987
Mon: Set 1/2" Bar & Cap #25832 by double proportionate measurement
Access: S05°E 16.89' N&T E. side 10" Cherry
S85°E 38.29' N&T S. side 18" Maple
S70°W 16.13' N&T N. side 8" Maple
- Larry Bryan, Cert. Survey, Rec. L. 5, P. 503 8/15/88
Mon: Found Bar & Cap 25832
Access: S05°E 16.89' N&T E. side 10" Cherry
S85°E 38.29' N&T S. side 18" Maple
S70°W 16.13' N&T N. side 8" Maple

APPROVED
County Remonumentation
Peer Review Group
31 OCT 97
NCC

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	20	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found L. Bryan Rerod and Cap as referenced in No. 2. Accepted this location as the careful and faithful re-establishment of the original corner position. Some remains of wire fence running East and West lies 18 feet South.

C. Description of monument for corner and accessories to perpetuate locating the position of the corner

Replaced the L. Bryan Rerod & Cap with a standard Shiawassee County Harrison Marker stamped "Remon 24622". The Marker is witnessed by the following accessories:

S80°W 16.42'	Set N&T #24622 in S. face 10" Hickory
N05°E 30.57'	Set N&T #24622 in E. face 8" Maple
East 8.56'	Set N&T #24622 in S. face 4" Ash
N65°E 38.06'	Set N&T #24622 in S. face 24" Ash

This location is 80± feet West of drain.

Signed by Mark L. VanRaemdonck
Surveyor's Michigan License No. 24622

Date OCT. 29, 1997

LIBER LR **PG** 221