

**SURVEY & REMONUMENTATION**

DEC 5 1993

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**REMONUMENTATION**

RECORDED  
 93 DEC -6 1110:59  
 REGISTER OF DEEDS  
 SHIAWASSEE COUNTY, MICH.

For corners in  
 Shiawassee

	(County)	Located In:		Corner Code #
		6N	1E	
1. Public Land Survey		T	R	K-12
		T	R	
		T	R	
		T	R	
2. Property Controlling in Section		S	T	R
		S	T	R
3. Miscellaneous Property in Sec.		S	T	R
		S	T	R

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Norman C. Caldwell, in a field survey on November, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		6		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

K-12 1/4 cor., Sec. 35 & 36, T6N-R1E

Wood post placed by J. Wampler, 1826, N24 1/2°E 55.5 lks. (36.63') 11" B. Oak S36 1/2°W 55.5 lks. (36.63') 14" Maple

Survey by L. Mason, Co. Surveyor, 1880, recorded in Book D & E, pgs. 60 & 61, Monument not given S05°W 37.25 lks. (24.58') 5" Y. Oak N82 3/4°W 90 2/3 lks. (59.55') 16" Y. Oak

Unrecorded survey by A. F. Miller, 1981, Set rerod w/cap at anchor post S10°E 5.40' N & T 18" Maple N75°W 13.60' N & T 15" Wild Cherry N05°W 10.70' N & T 24" Wild Cherry N85°E 19.00' n & T 4" Locust

Surveys by M. L. Vanraendonck, 1985 & 1987, recorded in L. 4, pgs. 507 & 508 of Surveys and L. 2, pg. 459 of Corners Fnd. rerod w/cap #12024 West 15.55' Nail S. face 30" Oak N75°E 13.6' Nail S. face 12" Y. Birch N10°W 10.75' Nail SW face 24" Y. Birch S20°E 5.28' Nail SE face 24" Maple

Surveys by L. A. Bryan, 1986 & 1987, recorded in L. 5, pgs. 676 & 677 of Surveys and L. 2, pg. 478 of Corners Fnd. 1/2" bar & cap #12024 E. side cor. post at 4 way fence inter. N05°W 10.20' Fnd. N & F SW side 20" Cherry N80°W 13.15' Fnd. N & F S. side 14" Cherry S45°E 5.82' Fnd. N & F NE side 20" Maple

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

K-12 1/4 cor., Sec. 35 & 36, T6N-R1E

Fnd. 1/2" rod w/cap #12024 E. side 4 way fence inter. per L. 2, pgs. 459 & 478 of Corners and L. 4, pgs. 507 & 508 & L. 5, pgs. 676 & 677 of Surveys. Replaced with a standard 20" Harrison marker as approved by the Shiawassee County Peer Review Group and is accepted as the best available evidence of the position of the original corner.

NOTE: In excavation, found a second 1/2" bar directly below.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

K-12 1/4 cor., Sec. 35 & 36, T6N-R1E

Fnd. 1/2" rod w/cap #12024 E. side 4 way fence inter. per L. 2, pgs. 459 & 478 of Corners and L. 4, pgs. 507 & 508 & L. 5, pgs. 676 & 677 of Surveys. Replaced with a standard 20" Harrison marker as approved by the Shiawassee County Peer Review Group and is accepted as the best available evidence of the position of the original corner. N70°W 13.13' Fnd. N & F, Reset N & T #12018 above, S. face 15" Cherry (R) N05°W 9.55' Set N & T #12018 SW root 28" Cherry (R - tree) S30°E 5.47' Set N & T #12018 NE face 26" Maple (R - tree) N88°W 14.62' Set N & T #12018 N. face 60" Oak



Signed by Norman C. Caldwell  
 Surveyor's Michigan License No. 12018

Date 2 DEC 93

**IRFR DC 110**