

**SURVEY &
REMONUMENTATION**

990101993

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
REMONUMENTATION

RECORDED

30 DEC -6 AM 11:00

REGISTER OF DEEDS

Norman C. Caldwell
SHIAWASSEE COUNTY, MICH.

For corners in
Shiawassee

	Located In:		Corner Code #
	6N	1E	
1. Public Land Survey	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Norman C. Caldwell November 93
I, _____, in a field survey on _____, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-13 Twp. cor., common to T5 & 6N - R1 & 2E

Wood post placed by J. Wampler, 1824
S29°W 8 lks. (5.28') 23" W. Oak
N42°W 32 lks. (21.12') 23" W. Oak

Survey by M. L. Vanraemdonck, 1983, recorded in L. 4, pg. 49 of Surveys,
Fnd. 3/4" iron rod
S45°W 10.13' Nail 12" Oak
North 25.25' Nail 23" Oak
S45°E 5.70' Nail 13" Oak

Surveys by J. F. Quine, 1967 - 1975, recorded in L. 1, pg. 558 of Corners and Field Book 13, pg. 111, reestablished set 5/8" x 24" iron rod stake in evidence of old corner post hole. Put stones around it and set pointed stone on S. side iron
N05°W 26.2' 24" Oak
SW 10.7' 10" Oak
ESE 6.0' 12" Oak
NE 18.9' 6" Hickory
ENE 2.0' (1.6' E & 1.0' N)
NEW fence cor. post (Ref. to center)

Unrecorded survey by A. F. Miller, 1978,
Fnd. iron rod
N05°W 26.20' 30" Oak
S45°W 10.70' 12" Oak
S65°E 6.00' 14" Oak
N45°E 18.90' 8" Hickory

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-13 Twp. cor., common to T5 & 6N - R1 & 2E

Fnd. 5/8" rod surrounded by rocks in old N. S. E. W. fence per L. 1, pg. 558 of Corners & L. 4, pg. 49 of Surveys. Also, fnd. 1/2 rod w/cap #12024 (Miller) along side. Replaced with a 20" standard Harrison marker as approved by the Shiawassee County Peer Review Group and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-13 Twp. cor., common to T5 & 6N - R1 & 2E

Fnd. 5/8" rod surrounded by rocks in old N. S. E. W. fence per L. 1, pg. 558 of Corners & L. 4, pg. 49 of Surveys. Also, fnd. 1/2 rod w/cap #12024 (Miller) along side. Replaced with a 20" standard Harrison marker as approved by the Shiawassee County Peer Review Group and is accepted as the best available evidence of the position of the original corner.
S45°W 10.66' Fnd. overgrown nail, reset N & T #12018 W. face 15" Oak (R)
N05°W 25.83' Fnd. N & T #25832 SW face 30" Oak (R)
N65°W 24.37' Set N & T #12018 S. face 12" Hickory
S55°E 12.18' Set N & T #12018 SSW face 6" Oak



Signed by *Norman C. Caldwell*

Date 2 DEC 93

Surveyor's Michigan License No. 12018