

**SURVEY &  
REMONUMENTATION**

NOV 10 1997

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

97 NOV -6 PM 2:37

COMMISSION

REGISTER OF DEEDS  
*Gayle Shultz*  
SHIAWASSEE COUNTY, MICH.

For corners in

<u>Shiawassee</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>2E</u>	<u>K-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____	Recorded Plat _____	
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Mark L. VanRaemdonck, in a filed survey on June 5, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- Original: Joseph Wampler, D. S.  
Mon: Wood Post  
Access: W Oak 13 S 9 1/2 W 177 LKS  
B Oak 18 S 43 E 165 LKS
- Ezra Mason, County Surveyor, Book B-C, P. 146-147, 12/2-3/1868  
Mon: None Given  
Access: S36 1/2 W 45 4" Sugar  
N28 3/4 W 65 5" Sugar
- Bernard Griggs, R. L. S. #14763, Cert. Survey, Rec. L. 2, P. 113-120, 11/18/74  
Mon: Found 1" Pipe  
Access: West 32.89' C. P. Co. Pipe  
S20 E 98.65' Nail in Pole  
S30 W 114.86' Nail in P. P.
- Mark L. VanRaemdonck, Unrecorded Survey 12/4/86  
Mon: None Given  
Access: Bearings and distances to other Section corners

(Continued on next page)

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	5	4	3	2	1							
3													
4	7	6	5	4	3	2	1						
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner

Found 3/4" Pipe as referenced in No. 2, 3, 4 and 5. Accepted the pipe as the location of the original corner location based on the best available evidence. Found no conflicting evidence.

C. Description of monument for corner and accessories to perpetuate locating the position of the corner

Removed 3/4" pipe and installed a standard Shiawassee County Harrison Marker, stamped "Remon 24622". The marker is witnessed by the following accessories:

- North 2640.64' Harrison Marker at K-9
- West 4.24' Centerline asphalt surface
- West 33.00' 2" Pipe Cons. Power Co. Property corner
- East 43.45' 2" Pipe corner fence post
- S30 W 60.55' N&T #24622 in E. face 12" Cedar
- South 2631.97' Harrison Marker at K-11

Signed by *Mark L. VanRaemdonck*

Date OCT 30, 1997

Surveyor's Michigan License No. 24622

SHEET #1 OF 2

LIBERALS R PG 228

A. Description of original monument and accessories and/or subsequent restoration:

(Continued from front)

5. Mark L. VanRaemdonck, Cert. Survey Rec. L. 7, P. 042 6/30/1994  
Mon: Found 3/4" Pipe  
Access: West 4.24' Centerline asphalt  
West 32.98' 2" Pipe Con. Power Prop. Cor.  
East 43.45' 2" Pipe Fence Cor. Post  
S30°W 60.70' Set N&T E. face 12" Cedar
  
6. Mark L. VanRaemdonck, Cert. Survey Rec. L. 7, P. 339  
Mon: Found 3/4" Pipe  
Access: West 4.24' Centerline asphalt  
West 32.98' 2" Pipe Con. Power Prop. Cor.  
East 43.45' 2" Pipe Fence Cor. Post  
S30°W 60.70' Set N&T E. face 12" Cedar

SURVEY &  
REMONUMENTATION

NOV 10 1997

COMMISSION

SHEET #2 OF 2