

**SURVEY &  
REMONUMENTATION**

DEC 15 1993

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

93 DEC -6 AM 10:59

REGISTER OF DEEDS

*James J. Sullivan*  
SHELBY COUNTY, MICH.

For corners in  
Shiawassee

**REMONUMENTATION**

Located In: Corner Code #

(County)

6N 2E K-13

1. Public Land Survey	T	R	
	T	R	
	T	R	
	T	R	
2. Property Controlling in Section	S	T	R
	S	T	R
3. Miscellaneous Property in Sec.	S	T	R
	S	T	R

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman C. Caldwell, in a field survey on November, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

K-13 Sec. cor., 35 & 36, T6N-R2E  
Wood post placed by J. Wampler 1826, N71°E 45 lks. (29.70') 10" W. Oak N38°W 61 lks. (40.26') 10" W. Oak  
Survey by L. Mason, Co. Survey, 1876, recorded in Book D, pg. 124, shows dimensions for a breakdown of the S 1/2 Section 36

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

K-13 Sec. cor., 35 & 36, T6N-R2E  
Fnd. 6" x 6" x 12" pointed rock on top of 24" flat rock 23' East of R.R. Spike - previously used as a common township corner. This corner is **NOT** common (GLO set post for Sec. 1 & 2, T5N-R2E 33 lks. (21.78') W. of post for Sec. 35 & 36, T6N-R2E). Pointed rock fits well with the measurements of the Co. Surveyor's records and other collateral evidence and is accepted as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

K-13 Sec. cor., 35 & 36, T6N-R2E  
Fnd. 6" x 6" x 12" pointed rock on top of 24" flat rock 23' East of R.R. Spike - previously used as a common township corner. This corner is **NOT** common (GLO set post for Sec. 1 & 2, T5N-R2E 33 lks. (21.78') W. of post for Sec. 35 & 36, T6N-R2E). Pointed rock fits well with the measurements of the Co. Surveyor's records and other collateral evidence and is accepted as the best available evidence of the position of the original corner.  
West 23.04' Fnd. R.R. Spike @ Sec. cor. 1/2, T5N-R2E  
West 3.11' North leg traffic arrow sign  
N50°W 94.19' Fnd. Spike & Tag NE face Power Pole  
N70°E 106.74' SW cor. garage foundation  
N80°E 22.47' Top center tele. riser



Signed by *Norman C. Caldwell* Date 2 DEC 93  
Surveyor's Michigan License No. 12018