

SURVEY & REMONUMENTATION

DEC 15 1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

93 DEC -6 AM 10:59

For corners in
Shiawassee

REMONUMENTATION

Located In: Corner Code #

(County)	Located In:	Corner Code #
1. Public Land Survey	T 6N R 2E	L-13
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

REGISTER OF DEEDS
SHIWAASSEE COUNTY, MICH.

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman C. Caldwell, in a field survey on November, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-13 S 1/4 cor., Sec. 36, T6N-R2E

Wood post placed by J. Wampler, 1826,
N89°E 45 lks. (29.7') 20" W. Oak
N65°W 27 lks. (17.82') 13" W. Oak

Survey by E. Mason, 1869, recorded in Book A, pg.
188, S.C.R.
Showed breakdown of S 1/2 of Sec. 36

Survey by E. Mason, 1863, recorded in Book
B, pg. 124 - 125, S.C.R.
Showed breakdown of Sec. 36

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13 S 1/4 cor., Sec. 36, T6N-R2E

Found evidence of old wood post (discolored soil profile to point), fits well with old fence N-E-W.
Found no conflicting evidence. Set standard 20" Harrison marker as approved by the Shiawassee County Peer Review Group and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13 S 1/4 cor., Sec. 36, T6N-R2E

Found evidence of old wood post (discolored soil profile to point), fits well with old fence N-E-W.
Found no conflicting evidence. Set standard 20" Harrison marker as approved by the Shiawassee County Peer Review Group and is accepted as the best available evidence of the position of the original corner.
N20°W 13.12' Set N & T #12018 E. face 10" Hickory
S65°E 14.50' Set N & T #12018 SSW face 18" Oak
N80°W 32.85' Set N & T #12018 N. face 9" Oak
S60°W 10.22' Set N & T #12018 WNW face 6" Tw. Hickory
North 1'± Set REI Carsonite Witness Post



Signed by Norman C. Caldwell (Date) 2 DEC 93
Surveyor's Michigan License No. 12018