

**SURVEY &
REMONUMENTATION**

NOV 10 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

97 NOV -6 PM 2:37

For corners in **COMMISSION**

Shiawassee (County)	Located in:	Corner Code #
1. Public Land Survey	T 6N R 2E	M-9
	T R	
	T R	
	T R	
2. Property Controlling In Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

REGISTER OF DEEDS
Kaye Shubbs
SHIAWASSEE COUNTY, MICH.

Register of Deeds Stamp & File Number

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

I, Mark L. VanRaemdonck, in a filed survey on June 5, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Original John Mullett, D. S.
Mon: Wood Post
Access: B Oak 6 S26 1/2 W 155
do 8 N63W 170
- Mark L. VanRaemdonck, Cert. Survey Rec. L. 3, P. 181 4/12/1979
Mon: "T" Iron
Access: East 24.00' Nail in Post
S30°W 36.15' P. K. in 3" Tree
S10°W 85.35' P. K. in 30' Maple
S60°W 34.35' P. K. in Mail Box Post
- Mark L. VanRaemdonck, L. C. R. C. Rec. L. 2, P. 191, 6/29/79
Mon: Found "T" Iron
Access: East 24.00' Nail in Post
S30°W 36.15' P. K. in 3" Tree
S10°W 85.35' P. K. in 30' Maple
S60°W 34.35' P. K. in Mail Box Post
- Mark L. VanRaemdonck, L. C. R. C. Rec. L. 2, P. 664 8/25/89
Mon: Found "T" Iron
Access: S55°W 47.80' Set N&T N face 12" Elm
S40°W 35.68' Set N&T E face 8" Trunk twin Walnut
S30°E 23.58' Set N&T W face 6" Elm
N15°W 102.46' Set N&T E face 12" Elm

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

APPROVED
County Remonumentation
Peer Review Group

*NCC
31 OCT 97*



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found "T" Iron as referenced in No. 2, 3 and 4 above. Found no conflicting evidence. Accepted this location as the position of the original corner based on the best available evidence.

C. Description of monument for corner and accessories to perpetuate locating the position of the corner

Removed "T" Iron and installed a standard Shiawassee County Harrison Marker stamped, "Remon 24622." The marker is witnessed by the following accessories:
 S25°E 23.33' Set N&T 24622 in W. face 12" Elm
 S30°W 35.60' Set N&T 24622 in E. face Twin 12" Ash
 S45°W 45.77' Set N&T in N. face 12" Elm
 N45°W 59.35' Rerod & Cap #24622 in Shoulder

Signed by Mark L. VanRaemdonck
Surveyor's Michigan License No. 24622

Date OCT. 29, 1997

LIBER LR PG 232