

SURVEY & REMONUMENTATION

NOV 10 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

97 NOV -6 PM 2:38

REGISTER OF DEEDS

Kayla Smith
 SHIAWASSEE COUNTY, MICH.

For corners in

<u>Shiawassee</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T_6N R_4E	K-9
	T_____ R_____	_____
	T_____ R_____	_____
	T_____ R_____	_____
2. Property Controlling In Section	S_____ T_____ R_____	_____
	S_____ T_____ R_____	_____
3. Miscellaneous Property in Sec.	S_____ T_____ R_____	_____
	S_____ T_____ R_____	_____
4. Lot No. _____	Recorded Plat _____	
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Mark L. VanRaemdonck, in a filed survey on March 20, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Original John Mullett, D.S. 1823
 Mon: Wood Post
 Access: Beech 15 S28W 57 LKS
 Beech 9 N47E 10 LKS
- Edwin J. McCombs, L. C. R. C. Rec. L. 1, P. 53 6/29/72
 Mon: Found 3/4" pipe in road intersection
 Access: N40W 48.5' T. Pole
 N50W 38.54 Road Sign
 S50W 46.7 Pipe Line Marker
- Consumers Power Co.
 Unrecorded Survey 6/16/72
 Mon: Found 3/4" Pipe 0.5' E of centerline blacktop
 Access: T. Pole N40W 48.5
 Rd. Sign N50W 38.54
 Pipeline marker S50W 46.7
- Norm C. Caldwell, L. C. R. C. Rec. L. 2, P. 607
 Mon: Found R. R. Spike Over 5/8" Pipe
 Access: N30W 48.46 PK&T E. face T.P.
 N45W 47.44 Chis. Not. W. edge Rd. Sign Post
 S45W 46.35 Chis Not. S. edge Gas P. L. sn post
 S70E 76.07 Pun. Hole T. C. W. end 15' CMP
 N40E 47.34 Conc. Mon. (Top 12" Brok. & Bent)
- Mark L. VanRaemdonck, Cert. Survey Rec. L. 6, P. 835, May 26, 1994
 Mon: Found 3/4" Pipe in Road Intersection
 (Found R.E.I. Iron in Mon. Box)
 Access: N40W 48.5' T. Pole
 N50W 38.54 Road Sign
 S50W 46.7 Pipe Line Marker

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found R.E. I. Rerod & Cap in Mon. Box as referenced in No. 3 above and is accepted as the best available evidence of the position of the original corner. Found no conflicting evidence.

C. Description of monument for corner and accessories to perpetuate locating the position of the corner

Installed a standard Shiawassee County Harrison Marker, stamped "Remon 24622." The marker is witnessed by the following accessories:
 N45°E 64.41' P. K. & Tag #24622 in W. face 6" Pine
 S70°E 72.70' Rivet Top Cen. W. end 12" CMP Culv.
 S35°W 55.27' Top Cen. Gas Valve North one of two valves
 N40°W 57.27' Top Cen. Tele. Cable Box

Signed by *Mark L. VanRaemdonck*
 Surveyor's Michigan License No. 24622

Date OCT 29, 1997

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS
 JAN 18, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	20	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

APPROVED
 County Remonumentation
 Peer Review Group

NCC
31 OCT 97



LIBER IR PG 240