

SEP 29 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 SEP -6 AM 11:05

REGISTER OF DEEDS

Shiawassee County, Mich. stamp with signature

For corners in

Table with columns: Shiawassee (County), Located In, Corner Code #. Rows include Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec.

Register of Deeds Stamp & File Number

APPROVED

County Remonumentation

Peer Review Group

8/16/94 M.L.V.

I, Norman C. Caldwell, in a field survey on July, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 2-13. Cell (12, 35) is shaded.

A. Description of original monument and accessories and/or subsequent restoration:

K-12 1/4 cor., Sec. 35 & 36, T6N-R4E

Wood post placed by J. Mullett, 18 Z 3 N87°E 39 lks. (25.74') 6" B. Ash S23 1/2°W 17 lks. (11.22') 7" B. Ash

Survey by J.S. Fokens, July 1977, recorded in L. 2, pg. 537 of Surveys Fnd. Boat Spike N45°W 65.70' C.P. Co. Gas Marker S80°E 35.90' Set PK 36" Maple East 33.03' C.P. Co. Rod & Cap West 33.00' REI Rod & Cap

Survey by A. Huggins Co. Surveyor, Feb. 1848, recorded in County Surveyors record Bk A pg. 62, S.C.R. Mon. & Refs. Not Given

Survey by M.L. Vanraemdonck, Dec. 1978, recorded in L. 3, pg. 183 of survey Fnd. boat spike (see L. 2, pg. 537 of surveys for refs.)

Survey by H.C. Main, County Surveyor, March 1870 recorded in Co. Surveyors record, BK C pg. 188-189 & BK A pg. 238-239.

Survey by N.L. Caldwell, Feb. 1989, recorded in L. 2, pg 605 of corners Fnd. Boat Spike per REI record 10-12-76 S40°W 29.68' R & C #20709 edge Road S30°E 26.85' R & C #20709 edge road N30°E 25.78' R & C #20709 edge road N40°W 70.8' Gas pipeline marker sign

Survey by E.J. McComb, C.P. Co., June 1972 recorded in L. 1, pg. 44 of corners, Set. Boat Spike N45°W 65.70' C.P. Co. gas line marker S80°E 35.90' 36" Maple

Surveys by M.L. Vanraemdonck, July 1992 & Dec. 1992, recorded L. 6, pg. 285 & pgs. 407-408 of surveys. Fnd. Boat Spike (see L. 2, pg. 605 of corners for refs.)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-12 1/4 cor., Sec. 35 & 36, T6N-R4E

Fnd. 1/2" rerod #12018 in mon. box, replaced w/std. 20" Harrison marker as approved by the Shiawassee County Remon. Peer Review Group and is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-12 1/4 cor., Sec. 35 & 36, T6N-R4E

Fnd. 1/2" rerod #12018 in mon. box, replaced w/std. 20" Harrison marker as approved by the Shiawassee County Remon. Peer Review Group and is accepted as the best available evidence of the position of the original corner.

S35°E 49.12' Set chis. "+" top cent. E. end 24" CMP S35°W 48.23' Set chis. "+" top cent. W. end 24" CMP N30°E 42.62' Set PK & Tag N. end E. guard rail N30°W 46.75' Set PK & Tag N. end W. guard rail

Signed by [Signature] Date 10/10/94

Surveyor's Michigan License No. 12018

