

NOV 10 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

97 NOV -6 PM 2:38

REGISTER OF DEEDS

Kaye Hubbs
SHIAWASSEE COUNTY, MICH.

For corners in

<u>Shiawassee</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T 6N R 4E	L-9
	T R	
	T R	
	T R	
2. Property Controlling In Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____	Recorded Plat _____	
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Mark L. VanRaemdonck, in a filed survey on March 20, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Original John Mullett 1823
Mon: Wood Post
Access: W. Oak 20 N2W 26 LKS
Maple 18 S18W 13 LKS
- Consumers Power Co
Unrecorded Survey 6/16/72
Mon: Found "T" Iron in line N&S Fence
Access: T. Pole North 31.91
SW cor house N40E 72.15
- Edwin J. McCombs, L.C.R.C. Rec. L. 1, P. 53 6/29/72
Mon: Found "T" Iron
Access: SW cor. house N40E 72.15
T. Pole North 31.91
- Mark L. VanRaemdonck, Cert. Survey Rec L. 6, P. 834, May 26, 1994
Mon: Found "T" Iron
Access: South 33.00' Rerod & cap #24622
S25W 30.77' Cen W. face 2" Scotch pine
S25E 44.06' Cen W. face 2" Ash
North 32.77' Cen W. face 2" Steel fence post

APPROVED
County Remonumentation
Peer Review Group

NCC
31 OCT 97

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found "T" iron as referenced in No. 4 above and is accepted as the best available evidence of the position of the original corner. Found no conflicting evidence.

C. Description of monument for corner and accessories to perpetuate locating the position of the corner

Removed "T" iron and installed a standard Shiawassee County Harrison Marker, stamped "Remon 24622." The marker is witnessed by the following accessories:

- | | | |
|-------|--------|--|
| North | 32.64' | 2" Steel Galv. Anchor Post |
| N25°E | 38.07' | 2" Steel Galv. Gate Post |
| N45°E | 48.07' | Set N&T #24622 in W. face 6" Scotch Pine |
| S20°W | 30.62' | Set N&T #24622 in E. face 4" Scotch Pine |

Signed by Mark L. VanRaemdonck

Date OCT. 29, 1997

Surveyor's Michigan License No. 24622

LIBERALS R PG 242