

**SURVEY & REMONUMENTATION COMMISSION**

SEP 29 1994

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 SEP -6 AM 11:05

REGISTER OF DEEDS

*Gayle Busha*  
SHIAWASSEE COUNTY, MICH.

For corners in

<u>Shiawassee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>4E</u>	<u>L-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Norman C. Caldwell, in a field survey on July, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

L-13 Std. 1/4 Cor., Sec. 36, T6N-R4E

Wood post placed by J. Mullett, 1848  
S31°W 13 lks. (8.58') 6" B. Ash  
N29°E 36 lks. (23.76') 9" Butternut

Survey by A. Huggins, Co. Surveyor, Feb. 1848 recorded in County Surveyors records BK A, pg. 62 S.C.R.  
Mon. & Refs. Not Given

Survey by J.F. Quine, 1966 recorded in Field Bk. 12, pg. 136  
Mon. Not Given

North 29.0' 3" Yellow Steel Post  
North 40.7' 12" Maple  
North 19.8' Cent. 4' sq. conc. C.B.  
SW 36.5' Cent. 4' sq. conc. C.B.

Survey by E.J. McCombs, C.P. Co. 1972 recorded in L. 1, pg. 44 of corners  
Fnd. R.R. Spike in CL Black top road  
South 44.30' 4" Poplar  
S20°E 53.00' 8" Oak  
N01°W 41.68' 8" Maple

Surveys by M.L. Vanraendonck, 19774 recorded in L. 2, pg. 575-576 & Pg. 624 of surveys.  
Set PK Nail

North 40.70' Set N & T 12" Maple  
S10°W 33.70' Set N & T Tele. Pole  
S05°W 48.26' Set N & T 10" Poplar  
North 19.80' Set N & T Top C.B.

Survey by J.S. Fokens, 1983 recorded L. 4, pg. 55 of surveys per L. 2, pg. 575-576 & pg. 624

Survey by N.C. Caldwell, 1989 recorded in L. 2, pg. 609 of corners and L. 5, pg. 227-231 of surveys.  
Fnd. PK Nail, replaced w/bar & cap #20709  
North 40.70' N & T 12" Maple  
S10°W 33.70' N & T NE fc. Power Pole  
North 19.8' Cent. 4' sq. conc. C.B.  
S45°W 36.5' Cent. 4' sq. conc. C.B.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: 8/16/94 MLV

L-13 Std. 1/4 Cor., Sec. 36, T6N-R4E

Fnd. rerod w/smashed cap in CL asphalt road per records (above), replaced w/a std. 20" Harrison marker and mon. box as approved by the Shiawassee County Remon. Peer Review Group and is accepted as the best available evidence of the position of the original corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13 Std. 1/4 Cor., Sec. 36, T6N-R4E

Fnd. rerod w/smashed cap in CL asphalt road per records (above), replaced w/a std. 20" Harrison marker and mon. box as approved by the Shiawassee County Remon. Peer Review Group and is accepted as the best available evidence of the position of the original corner.

S10°W 33.69' Fnd. N & T NE fc. Power Pole (R)  
North 19.88' Cent. 4' sq. conc. C.B. (R)  
S60°W 36.49' Cent. 4' sq. conc. C.B. (R)  
North 33.00' Fnd. 1/2" rerod w/cap #11192 (R)

Signed by *Norman C. Caldwell* Date \_\_\_\_\_

Surveyor's Michigan License No. 12018



**LIBER 1 PG**