

SURVEY & REMONUMENTATION

SEP 29 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED
94 SEP -6 AM 11:06
REGISTER OF DEEDS
Loye Shamba
SHIAWASSEE COUNTY, MICH.

For corners in

Shiawassee (County)	Located In:	Corner Code #
1. Public Land Survey	T 6N R 4E	M-12
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Norman C. Caldwell, in a field survey on July, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-12 E 1/4 cor., Sec. 36, T6N-R4E

Wood post placed by J. Mullett, 18 23
S46°W 24 lks. (15.84') 14" W. Ash
N30°W 78 lks. (51.48') 30" Oak

Unrecorded survey by E.S. Brewer, Oct. 1986,
Reinf. rod in gravel road
See L. 1, pg. 45 of corners for refs.

Survey by A. Huggins, County Surveyor,
Feb. 1848, recorded in County Surveyors
records BK A. pg. 62, S.C.R.
Mon. & Refs. Not Given

Survey by N.C. Caldwell, 1989 recorded in L. 5,
pgs. 227-231 of surveys, cor. ref. (pg. 228) appears
to be E 1/4 cor. Sec. 35, T6N-R4E

Survey by E.J. McCombs, C.P. Co.
1972, recorded in L. 1, pg. 45 of cors.
Set. reinforcing rcd on line from
N & S Sec. cor. & tnc to West
West 54.25' 24" Hickory
S70°E 22.65' 20" Hickory
N45°W 37.45' Catalpa

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-12 E 1/4 cor., Sec. 36, T6N-R4E

Fnd. 1/2" rerod per L. 1, pg. 45 of cor., replaced w/a std. 20"
Harrison marker as approved by the Shiawassee County Remon. Peer
Review Group and is accepted as the best available evidence of
the position of the original corner.

APPROVED
County Remonumentation
Peer Review Group
8/16/94 MLV

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-12 E 1/4 cor., Sec. 36, T6N-R4E

Fnd. 1/2" rerod per L. 1, pg. 45 of cor., replaced w/a std. 20"
Harrison marker as approved by the Shiawassee County Remon. Peer
Review Group and is accepted as the best available evidence of
the position of the original corner.
S60°E 22.61' Fnd. grown-in R.R. Spike W. fc. 24" Hickory (R)
N65°E 33.47' Fnd. N & T #11192 N. fc. 8" Ash
S70°W 24.13' Fnd. N & T #11192 S. fc. 8" Locust
West 33.09' Fnd. Landmark Rod & Cap
North 77.10' W 1/4 cor., Sec. 31, T6N-R6E



Signed by *Norman C. Caldwell*

Date 16 AUG 94

Surveyor's Michigan License No. 12018