

SURVEY & REMONUMENTATION

SEP 29 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 SEP -6 AM 11:05

REGISTER OF DEEDS

Kaye Shultz
 SHIAWASSEE COUNTY, MICH.

For corners in

<u>Shiawassee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>4E</u>	<u>M-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Norman C. Caldwell, in a field survey on July, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-13 Twp. cor., T6N-R4 & 5E, & T5N-R4 & 5E

Wood post placed by J. Mullet, 1823
 S60°W 22 lks. (14.52') 15" B. Oak
 N53°E 14 lks. (9.24') 10" Beech

Survey by E. J. McCombs, C.P. Co.
 1972 recorded in L. 1, pg. 44 of cors.
 Fnd. 3/4" iron bar in mon. box
 S45°W 58.15' 18" Hickory
 S45°E 51.38' Road sign
 N45°E 58.35' Power Pole

Survey by M.L. Vanraemdonck, 1977 recorded in L. 2, pg. 575-576 & Pg. 624 of surveys.
 Iron in mon. box
 S42°W 57.44' Set N & T 18" Hickory
 S40°E 49.40' Set N & T Tele. Pole
 S45°E 58.03' Set N & T Tele. Pole
 N30°E 78.42' Set N & T Tele. Pole

Survey by N.C. Caldwell 1989 recorded in L. 5, pgs. 227-231 of surveys
 Fnd. stone in mon. box, raised w/a 1/2" rebar & cap #20709
 See L. 2, pgs. 575-576 & Pg. 624 for refs.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-13 Twp. cor., T6N-R4 & 5E, & T5N-R4 & 5E

Fnd. 1/2" x 9" rerod per L. 5, pgs. 227-231 of surveys. During excavation found a 12" x 9" x 7" rock surrounded by smaller rocks and tile; replaced w/a std. 20" Harrison marker as approved by the Shiawassee County Peer Review Group and is accepted as the best available evidence of the position of the original corner.

APPROVED


County Remonumentation
 Peer Review Group

8/16/94 MLV

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-13 Twp. cor., T6N-R4 & 5E, & T5N-R4 & 5E

Fnd. 1/2" x 9" rerod per L. 5, pgs. 227-231 of surveys. During excavation found a 12" x 9" x 7" rock surrounded by smaller rocks and tile; replaced w/a std. 20" Harrison marker as approved by the Shiawassee County Peer Review Group and is accepted as the best available evidence of the position of the original corner.
 S22°W 57.47' Fnd. N & T NNE fc. 18" Hickory
 S35°E 52.91' Road sign
 S30°E 49.48' Fnd. N & TNW. fc. Tele. Pole
 N45°E 58.04' Fnd. N & T W. fc. Tele. Pole
 N10°E 78.38' Fnd. N & T S. fc. Tele. Pole



Signed by *Norman C. Caldwell*

Date 16 AUG 94

Surveyor's Michigan License No. 12018