

**SURVEY &
REMONUMENTATION**

SEP 29 1994

LAND CORNER RECORDATION CERTIFICATE 94 SEP -6 AM 11:07
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

For corners in **COMMISSION**

REGISTER OF DEEDS

Shiawassee (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>3E</u>	K-11
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____	
3. Miscellaneous Property in Sec.	S _____ T _____	
4. Lot No. _____, Recorded Plat _____	S _____ T _____	
5. Private Claims _____	S _____ T _____	

Raye Shulka
SHIAWASSEE COUNTY, MICH.

APPROVED
County Remonumentation
Peer Review Group
8/16/94 M.L.V.

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Norman C. Caldwell, in a field survey on July, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-11 Sec. cor., 25, 26, 35 & 36, T6N-R3E

Wood post placed by J. Mullett, 1823
N85°W 32.34 lks. (21.12') 12" W. Oak
S68°E 14 lks. (9.24') 7" W. Oak

Unrecorded survey by O.M. Elliot, April 1960, mon. & refs. not given.

Survey by A. Huggins, Co. Surveyor,
May 1849, recorded in BK A, pg. 83 &
BK B pg. 19 S.C.R.
No Refs or Mon. Given

Survey by J.F. Quine, Sept. 1973, recorded in L. 1, pg. 531 of surveys (Field Bk 14 pg. 60 9/67)
Reestablished by retracement of rec. Joslin survey & retracement of rec. plats. Drove iron stake, placed stones around it.
S45°W 5.6' 8" Hickory
Stake is 1.0' S. & 1.7' E. of broken cor. fnc. post

Survey by M. Holly, D.S. June 1854
recorded in BK B, pg. 53 S.C.R.
Indicates that he fnd. post.
No. Refs Given

Survey by E.S. Brewer, May 1977 recorded in L. 2, pg. 519 of surveys
Mon. & Refs. Not Given

Survey by E. Mason, Co. Surveyor June 1883
recorded in S.C.R. Co. Surveyors records
1879-1900, pgs. 104-105.
S34 1/2°E 39 1/4 lks. (25.90') 24" W. Oak
S26 3/4°W 58 lks. (38.28') 28" W. Oak

Survey by V. J. Lukezavitz, Jr., Oct. 1981, rec. L. 2, pg. 245 of cor.
Fnd. pipe & buried rocks ± 1.7' E of broken fnc. post ± 1.0' South of same, checked access. & conn. to 8" Hickory
S45°W 5.7' Gould tag SE fc. 10" Hickory
N04°W 51.78' Gould tag W fc. tri. Ash
N05°W 11.2' Gould tag fc. old fnc. post
S45°E 6.9' Gould tag NE fc. 6" Tree

Survey by E. F. Joslin, April 1900, recorded
in S.C.R. County Surveyors record 1879-1900
Mon. Not Given
S70°W 32 lks. (21.12') 12" Elm

Surveys by M. Vanraendonck, 1983-1984, rec. L. 4, pgs. 40-41 and pg. 215 of surveys
Mon - Metal Pipe
Refs - See L. 2, pg. 245 of corners

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-11 Sec. cor., 25, 26, 35 & 36, T6N-R3E

Fnd. 3/4" pipe 18" long surrounded by rocks per Joslins survey, L. 1, pg. 531, L. 2, pg. 519 & L. 4, pgs. 40-41 & 215 of surveys and L. 2, pg. 245 of corners. Replaced pipe w/a std. 20" Harrison marker as approved by the Shiawassee County Peer Review Group and is accepted as a careful and faithful perpetuation of the position of the original corner.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

11 Sec. cor., 25, 26, 35 & 36, T6N-R3E

Fnd. 3/4" pipe 18" long surrounded by rocks per Joslins survey, L. 1, pg. 531, L. 2, pg. 519 & L. 4, pgs. 40-41 & 215 of surveys and L. 2, pg. 245 of corners. Replaced pipe w/a std. 20" Harrison marker as approved by the Shiawassee County Peer Review Group and is accepted as a careful and faithful perpetuation of the position of the original corner.
S55°W 5.70' Fnd. N & T SE fc. 12" Hickory (R)
N85°W 24.83' Set N & T #12018 S. fc. 10" Hickory
N15°W 24.94' Set N & T #12018 SW fc. 4" Ash
N08°W 32.16' Set N & T #12018 W. fc. most W'ly trunk of 18" Ash

ed by *Norman C. Caldwell* Date _____
Surveyor's Michigan License No. 12018



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983