

**SURVEY &
REMONUMENTATION**

SEP 29 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE 94 SEP -6 AM 11:06
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

REGISTER OF DEEDS

Kaye Shubba
SHIAWASSEE COUNTY, MICH.

For corners in

<u>Shiawassee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 6N R 3E	L-11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Norman C. Caldwell, in a field survey on July, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

L-11 1/4 cor., Sec. 25 & 36, T6N-R3E

Wood post placed by J. Mullett, 1823
N08°E 129 lks. (85.14') 13" B. Oak
S14°W 109 lks. (71.94') 6" Tamarack

Unrecorded survey by J. F. Quine, Aug. 1964,
recorded in Field Book #7, Pgs. 74-75
Cor. position occupied by 8" diam. wooden cor.
post 4' high. Fnc. runs E-W and N.

Survey by A. Higgins, Co. Surveyor,
May 1849, recorded County Surveyors
record Book A pg. 83 & CO. Surveyors
record Bk B pg. 19, S.C.R.
Mon. & Refs. Not Given

Unrecorded surveys by E.E. Anderson, Dec. 1976,
Set. iron at fnc. cor. w/wire to North
N30°E 9.25' to 6" Locust
West 11.75' to fnc. post
S15°W 9.75' to 12" locust (dead 6/94)

Survey by E. Mason, Co. Survey, June
1923, recorded in County Surveyors
records 1879-1900, pgs. 104-105, S.C.R.
S42°E 35 1/2 lks. (23.43') 10" Tamarack

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-11 1/4 cor., Sec. 25 & 36, T6N-R3E

Fnd. 3/8" rod w/cap #11495 against S. side 8" diam. wood post 4' high
fnc. running E-W & N per Quines and Andersons records. Replaced 3/8"
rod w/a std. 20" Harrison marker as approved by the Shiawassee County
Peer Review Group and is accepted as the best available evidence of the
position of the original corner.


APPROVED
County Remonumentation
Peer Review Group
8/16/94 M.L.V.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-11 1/4 cor., Sec. 25 & 36, T6N-R3E

Fnd. 3/8" rod w/cap #11495 against S. side 8" diam. wood post 4' high
fnc. running E-W & N per Quines and Andersons records. Replaced 3/8"
rod w/a std. 20" Harrison marker as approved by the Shiawassee County
Peer Review Group and is accepted as the best available evidence of the
position of the original corner.

West 11.69' Fnd. Nail S. fc. fnc. post (R)
N55°E 9.36' Set N & T #12018 SE fc. 14" Locust (R)
N63°W 21.41' Set N & T #12018 S. fc. 12" Locust
S06°W 27.81' Set N & T #12018 W. fc. 8" Locust



Signed by *Norman C. Caldwell* Date 16 AUG 94
Surveyor's Michigan License No. 12018