

**SURVEY &
REMONUMENTATION**

NOV 10 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

97 NOV -6 PM 2:38

For corners in

Shiawassee _____ (County)	Located in:	Corner Code #
1. Public Land Survey	T_6N R_3E _____	M-9 _____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling In Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REGISTER OF DEEDS
Gayle Shultz
SHIAWASSEE COUNTY, MICH.

Register of Deeds Stamp & File Number

I, Mark L. VanRaemdonck, in a filed survey on March 21, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Original: John Mullett, DS 1823
Mon: Wood Post
Access: W. Oak 14 S19°W 46
B. Oak 18 N39°W 44
- F. A. Gould, Book 12, Page 112 June 1949
Mon: 1 1/2" Pipe, 2' Long
Access: W. Oak 12" N35°E 51.2'
Wild Cherry 15" N30°W 61.4'
B. Oak 12" S40°W 51.1'
B. Oak 10" S45°E 41.0'
- O. M. Elliot, Book 19, Page 30 7/25/1951
Mon: Not Given
Access: Oak 10" SW 48
Oak 36" West 84
- Jan S. Fokens, L. C. R. C. Rec. Liber 2, Page 90, 5/1/1977
Mon: Found 1 1/2" Iron pipe
Access: S50°E 40.20' P. K. Nail 10" Oak
S20°W 50.73' P. K. Nail 14" Stump
N50°W 40.85' P. K. Nail 8" Walnut
- Mark L. VanRaemdonck, Cert. Survey, Rec. Liber 7, Page 025, 10/10/1994
Mon: 1 1/2" Pipe
Access: N30°W 61.4' 15" Cherry
N35°E 51.2' 12" Oak
S40°W 51.1' 12" Oak

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

APPROVED

County Remonumentation
Peer Review Group

*NCC
31 OCT 97*



B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found 1 1/2" Pipe as referenced in No. 2, 3, 4 and 5 above. I accepted this location as the original corner position based on the best available evidence.

C. Description of monument for corner and accessories to perpetuate locating the position of the corner

Replaced pipe with standard Shiawassee County Harrison Marker, stamped "Remon 24622." The marker is witnessed by the following accessories:

- S30°W 67.48' N&T #24622 E. face 36" Oak
- West 15.52' N&T #24622 N. face Wood Anchor Post
- N60°W 41.05' N&T #24622 SE face 18" Walnut
- S45°E 41.23' N&T #24622 SE face 18" Oak
- South 20.98' Rerod & Cap

Signed by *Mark L. VanRaemdonck*

Date OCT. 28, 1997

Surveyor's Michigan License No. 24622