

**SURVEY &
REMONUMENTATION**

SEP 29 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 SEP -6 AM 11:06

COMMISSION

REGISTER OF DEEDS

Kyle Shultz
SHIAWASSEE COUNTY, MICH.

For corners in

Shiawassee (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>6N</u> R <u>3E</u>	M-11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Norman C. Caldwell, in a field survey on July, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-11 Sec. cor., Common to Sec. 25 & 36, T6N-R3E & Sec. 30 & 31, T6N-R4E

Wood post placed by J. Mullett, 1823
N05°W 187 lks. (123.42') 14" W. Oak
S11°W 103 lks. (67.98') 9" W. Oak

Survey by K. R. Piotrowski, March 1974, recorded
in L. 1, pg. 207 of corners
Fnd. T-bar, agrees w/original ties, at edge of
gravel road.

Survey by E. Mason, Co. Surveyor
June 1883, recorded in county
surveyors records 1879-1900 pgs.
104-105 S.C.R.

S55°W 32.52' 18" Clump of Oaks
N30°W 25.07' 33" Oak
N40°E 77.00' 12" Wild Cherry

Mon. - Not Given
S40 1/2°E 56 lks. (36.96') 14" W. Oak
N33 1/2°W 40 lks. (26.40') 18" B. Oak

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-11 Sec. cor., Common to Sec. 25 & 36, T6N-R3E, & Sec. 30 & 31, T6N-R4E

Fnd. T-bar at edge of gravel road (Geek Road) per L. 1, pg. 207 of
corners, replaced w/std. 20" Harrison marker as approved by the
Shiawassee County Peer Review Group and is accepted as the best
available evidence of the position of the original corner.

Measurements along the range line agree with E. Mason Survey of 1883.

APPROVED

County Remonumentation
Peer Review Group

8/16/94 M.L.V.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-11 Sec. cor., Common to Sec. 25 & 36, T6N-R3E, & Sec. 30 & 31, T6N-R4E

Fnd. T-bar at edge of gravel road (Geek Road) per L. 1, pg. 207 of
corners, replaced w/std. 20" Harrison marker as approved by the
Shiawassee County Peer Review Group and is accepted as the best
available evidence of the position of the original corner.

N30°W 22.06' Set N & T #12018 N. fc. 33" Cherry
S60°W 37.60' Set N & T #12018 N. fc. 14" Oak
S40°E 49.12' Set N & T #12018 N. fc. Tri Oak (10" Ave)
West 26.09' Set N & T #12018 N. fc. 8" Oak



Signed by *Norman C. Caldwell*

Date 16 AUG 94

Surveyor's Michigan License No. 12018