

**SURVEY & REMONUMENTATION**

MAY 28 1997

COMMISSION

**REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

96 AUG 16 PM 2:37

REGISTRAR OF DEEDS

*Gayle Swisher*  
SHIAWASSEE COUNTY, MICH.

For corners in Shiawassee Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

1. Public Land Survey T 7N R 1E D-02 (W)  
1/4 5 (w/4 5)

2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

I, Norman C. Caldwell, in a field survey on April 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-02 Closing West 1/4 Cor., Sec. 5, T7N-R1E

This position not established by the original government survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-02 Closing West 1/4 Cor., Sec. 5, T7N-R1E

Fractional Section 5 is not further divided or protracted for division on the original government plat.

Placed this position on the Michigan Meridian at 2640' northerly of the SW corner of Section 5 in accord with the Manual of Instructions for the survey of the Public Lands of the United States, 1973 edition, section 3-43, and the technical bulletin entitled Restoration of Lost or Obliterated Corners & Subdivision of Sections, 1974 edition, page 31.

Upon excavation, we found a cluster of 6" x 10" stones at this position. There is no indication of the origin of this monumentation. Approved by the joint Clinton/Shiawassee County Remonumentation peer group on 22 May 1996.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


D-02 Closing West 1/4 Cor., Sec. 5, T7N-R1E

Found cluster of 6" x 10" stones on the Michigan Meridian at 2640' northerly of the Closing Southwest corner of Section 5. Placed a standard Harrison monument at this position, in a monument box in the physical centerline of Meridian Road.

References:

- N 20 W 111.58' 6" Thorn Apple
- S 45 W 35.73' 14" Elm
- S 35 W 52.00' 4" Ash
- S 15 W 111.14' 10" Elm

**APPROVED**  
*5/22/96 MLV*  
County Remonumentation  
Peer Review Group



Signed by *Norman C. Caldwell* Date 31 MAY 1996

Surveyor's Michigan License No. 12018

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983  
ADAPTED FOR WORD PROCESSING MARCH, 1993

**LIBER 1 R PG 151**