MAY 2 8 1997

## REMONUMENTATION

## RECORDED

COMMISSION

## LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER OF DEEDS

96 AUG 16 PM 2: 37

For corners in		<u>.</u>		I b	
Shiawassee (County)	Located in:	Corner Code #	. SHL	Jaya Ludaa AWASSEE COUNTY, MICH.	
1. Public Land Survey	T 7N R 1E T R T R	D-03 (SW 5)		,	
<ul><li>2. Property Controlling in Section</li><li>3. Miscellaneous Property in Sec.</li></ul>	T R S T R S T R S T R S T R		Register of Dec	eds Stamp & File Number	•
4. Lot No, F 5. Private Claims	Recorded Plat		1 A B C	D E F G H I J K L	М
do hereby certify that under in lines 1 and 2 above wer current manual of survey ins Management or by a decree above were in conformance Court of Law; established	e in conformance with regulations tructions of the United States Depo of a Court of Law and/or that the co- with the rules of the Michigan Boar	n April 1996, P.A. of 1970, the corner points mentioned and rules therefore as required in the artment of the Interior, Bureau of Landerner points mentioned in lines 3, 4 and 5 d of Land Surveyors or by a Decree of a re-monumented, recovered, found as	7 - : 8 - 19 · ·	8 9 10 11 12 17 16 15 14 13 20 21 22 23 24	
expressed below:  NOTE: Not more than on this certification	•	wn and range, may be recorded	10 30	29 28 27 26 25	
A. Description of origin	nal monument and accessories	and/or subsequent restoration:	12 31	32 33 34 35 36	
D-03 Closing Section	on Corner of 5 & 8, T7N,R1E	Middlebury Township.		W E	

Post placed by Robinson Thomas, 24 January 1831, the snow being at a depth of from 18 to 24 inches. References: N 38 E 19 lks (12.54') 16" W. Oak, S 22 E 62 lks (40.92') 6" Maple

Arden S. Pierson, P.S. #13039, in a survey dated May, 1977, recorded in Liber 2 at pages 555 & 556, and an L.C.R.C. dated 9/22/77 and recorded in Liber 2 at page 48, established this position by intersection of the Meridian with the Section Line extended from the east. He placed a 1/2" bar and marked the following references: S 25 E 158.63' N.W. corner of house, S 63 E 39.05' road sign post, S 40 E 181.95' N.E. corner of house.

Mark L. VanRaemdonck, P.S. #24622, in a survey dated 29 April 1991 and recorded in Liber 6 at pages 105 & 106, found a 1/2" bar and marked the following references: S 25 E 158.63' N.W. corner of house, S 63 E 39.05' road sign post, S 40 E 181.95' N.E. corner of house.

- В. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- D-03 Closing Section Corner of 5 & 8, T7N,R1E, Middlebury Township.

Found record 1/2" bar in a monument box on the Michigan Meridian.

There is no apparent conflicting evidence, and this position is accepted as a careful and faithful reestablishment of the position of the original corner

Approved by the joint Clinton/Shiawassee County Remonumentation peer group 22 May 1996.

- Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- D-03 Closing Section Corner of 5 & 8, T7N,R1E, Middlebury Township.

Found record 1/2" Bar in a monument box and replaced with a standard Harrison monument on the Michigan Meridian and in the centerline of the physical Meridian Road.

JAN, 28, 1971

158.53' N.W. corner of house (R) S 40 E 182.05' N.E. corner of house (R)

159.82' 12018 tag in W. face Power Pole N 10 E 50.35' center top of telephone riser

South

center of Wilkinson Road (East)

Surveyor's Michigan License No.

12018

IN THE CONTRACTOR OF SAFETY OF THE PROPERTY OF

NORMAN C. CALDWELL PROFESSIONAL SURVEYOR No. 12018

OF M/C4

Remonumentation Peer Review Group

REVISED MAY 14, 1975 REVISED JAN., 1983 ROCESSING MARCH, 1863