

SURVEY & REMONUMENTATION

MAY 28 1997

COMMISSION

**REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

85 AUG 16 PM 2:38

For corners in <u>Shiawassee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 7N R 1E	D-10 (W 1/4 29)
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REGISTER OF DEEDS
Kaye Shubert
SHIAWASSEE COUNTY, MICH.

Register of Deeds Stamp & File Number

I, Norman C. Caldwell, in a field survey on April 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-10 Closing West 1/4 Cor., Section 29, T7N-R1E

This position not monumented by the original government survey.
There is no record of subsequent surveys which may have established this position.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-10 Closing West 1/4 Cor., Section 29, T7N-R1E

Following an extensive search, it was determined that there is no monument representing this position and it is established on the Michigan Meridian at a mid point between the Closing Section Corners of Section 29.

There is no apparent conflicting evidence and this position is accepted as a careful and faithful determination of the position of the corner.

Approved by the joint Clinton/Shiawassee County Remonumentation peer group 22 May 1996.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-10 Closing West 1/4 Cor., Section 29, T7N-R1E

Placed a standard Harrison monument on the Michigan Meridian at a mid point between the closing section corners of section 29.

References:

- N 75 E 11.00' #12018 Tag in 8" Elm
- N 20 E 18.00' #12018 Tag in 6" Elm
- N 50 W 16.10' #12018 Tag in 10" Twin Box Elder
- S 50 W 17.65' #12018 Tag in 8" Elm



APPROVED
5/22/96 MLV
County Remonumentation
Peer Review Group

Signed by *Norman C. Caldwell* Date 31 MAY 1996
Surveyor's Michigan License No. 12018

LIBER I.R PG 159