

SURVEY & REMONUMENTATION

MAY 28 1997

COMMISSION

**REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

96 AUG 16 PM 2:38

REGISTER OF DEEDS

Gayle Hubbs
SHIAWASSEE COUNTY, MICH.

For corners in <u>Shiawassee</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 7N R 1E	D-11 (NW 32)
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Norman C. Caldwell, in a field survey on April 1996, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5			4	3	2	1					
3													
4	7	8			9	10	11	12					
5													
6	18	17			16	15	14	13					
7													
8	19	20			21	22	23	24					
9													
10	30	29			28	27	26	25					
11													
12	31	32			33	34	35	36					
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-11 Closing Section Corner of Sections 29 & 32, T7N-R1E

Post placed by Robinson Thomas, 24 January 1831
References: S 64 E 24 lks (15.85') 18" Elm
N 53 E 26 lks (17.16')

There is no record of any subsequent surveys utilizing this position.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-11 Closing Section Corner of Sections 29 & 32, T7N-R1E

Following an extensive search it is determined that there is no monument marking this position.

This position is determined by intersecting the Michigan Meridian with the extension of the west 1/2 mile of the line between Sections 28 & 33 as recently surveyed by John Quine, P.S. #10704 and recorded in Liber 7 at page 377.

There is no apparent conflicting evidence and this position is accepted as a careful and faithful re-establishment of the position of the original corner.

Approved by the joint Clinton/Shiawassee County Remonumentation peer group 22 May 1996.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-11 Closing Section Corner of Sections 29 & 32, T7N-R1E

Place standard Harrison monument at the intersection of the Michigan Meridian and the extended west 1/2 mile of the section line between sections 28 & 33

References:

S 45 E 19.05' #12018 Tag in 12" Basswood
East 12.15' #12018 Tag in 16" Oak
S 10 W 2.48' #12018 Tag in 10" Twin Basswood
N 25 W 10.26' #12018 Tag in 10" Aspen
N 15 E 14.50' Fence (East)



Signed by *Norman C. Caldwell* Date 31 MAY 1996

Surveyor's Michigan License No. 12018

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
ADAPTED FOR WORD PROCESSING MARCH, 1983

APPROVED
5/22/96 MLV
County Remonumentation
Peer Review Group

LIBER 1 R PG 160