

**SURVEY &  
REMONUMENTATION**

MAY - 1 1995

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

94 NOV 16 PM 3:43

For corners in **COMMISSION**

<u>Shiawassee</u>	Located in:	Corner Code #
(County)		
1. Public Land Survey	T <u>7N</u> R <u>1E</u>	<u>(K-11)</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REGISTER OF DEEDS  
*Gayle S. ...*  
SHIAWASSEE COUNTY, MICH.

**Register of Deeds Stamp & File Number**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Mark L. VanRaemdonck, in a filed survey on October 21, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the current points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1.) Original: Robinson Thomas, D.S. 1831.  
Monument: Wood post  
Accessories: B. Oak 8 N63°E 37 links  
do 4 N88°W 85 links
- 2.) E. L. Mason, Deputy County Surveyor. 3/7 1858  
Monument: Not given  
Accessories: B. Oak 12 S56°W 60 1/4  
B. Oak 12 S54°W 1/8
- 3.) R. Kraft: Unrecorded survey Section 25. 05/22/72  
Monument: "T" iron  
Accessories: Property corner 47.10' Northeast  
County road sign 45.8' Southeast  
County road sign 31.5' Northwest
- 4.) M. VanRaemdonck: Survey recorded Liber 4, page 109, 12/19/83.  
Monument: Found "T" iron  
Accessories: N45°W 30.25' Southeast face road sign post  
N45°E 38.0' Southwest face cable marker post  
S30°E 45.0' Northwest corner yield sign post  
S85°W 73.55' Northeast face 4" Blue Spruce

**APPROVED**

County Remonumentation  
Peer Review Group

*10/18/94 M.L.V.*

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Original monument and accessories have been obliterated. Accessories by E. L. Mason (03/07/1858) have been obliterated. Found "T" iron as referenced in no.'s 3 and 4 above. This location fits well with measurements along West line and with G.L.O. distance and County Surveyor's distances to M-11. Accepted this location as the best available evidence of the original corner location. Excavation for installation of Harrison marker provided no further evidence.

**C. Description of monument for corner and accessories to perpetuate locating the position of the corner:**

Set standard Harrison marker stamped "REMON 24622" and witnessed by the following accessories:  
N60°E 37.28' Top center telephone cable box  
N30°W 98.91' Set N&T in East face 12" Elm  
N10°W 100.53' Set N&T in West face 12" Elm  
S45°W 64.28' Center East face flag pole



Signed by *Mark L. VanRaemdonck*

Date Nov. 9, 1994

Surveyor's Michigan License No. 24622

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS JAN 18, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

**LIBER** 1R **PG** 85