

**SURVEY &
REMONUMENTATION**

MAY - 1 1995

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

94 NOV 16 PM 3:43

For corners in **COMMISSION**

<u>Shiawassee</u> (County)	Located in:	Corner Code #
	T <u>7N</u> R <u>1E</u>	<u>(K-12)</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
1. Public Land Survey	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REGISTER OF DEEDS
Sage Anthon
SHIAWASSEE COUNTY, MICH.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Mark L. VanRaemdonck, in a filed survey on October 21, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the current points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1.) Original: Robinson Thomas, D.S. 1831
 Monument: Wood post
 Accessories: W. Maple 12 S45°W 39
 do 5 N83°E 13

APPROVED

County Remonumentation
Peer Review Group

10/18/94 M.L.V.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original monument and accessories have been obliterated. County Surveyor records show use of the corner for subdivision of Section 36 but give no mention of monument or accessories (1858 by E. L. Mason and 1868 by Ezra Mason). Excavated with back hoe in the apparent location. Found a 12"± diameter stone with a broken dinner plate above directly in line with an old fence line running West. This location is approximately 5 feet East of the centerline of the gravel surface and is 0.9 feet South of the split of the distance between K-11 and K-13. Accepted this location as the faithful perpetuation of the original corner location.

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

Set standard Harrison marker stamped "REMON 24622" and witnessed by the following accessories:
 West 33.03' Rerod and cap #39096
 S15°E 52.82' Notch in top center North end 18" C.M.P. culv.
 S20°W 46.84' Top center West end 18" C.M.P. culv.
 S25°W 54.13' Spike and tag #39096 in East face 36" Oak
 N75°W 33.65' Set N&T East face 18" Oak



Signed by *Mark L. VanRaemdonck*
 Surveyor's Michigan License No. 24622

Date Nov. 9, 1994

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS JAN 18, 1971
 REVISED MAY 14, 1977
 REVISED JAN., 1988

LIBER IR **PG** 86

C. Description of monument for corner and accessories to perpetuate locating the position of the corner.