

**SURVEY & REMONUMENTATION**

NOV 10 1997

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED  
 97 OCT 15 PM 12:15  
 REGISTER OF DEEDS

*Kaye Shultz*  
 SHIAWASSEE COUNTY, MICH.

For corners in Shiawassee (County) Located In: Middlebury Township Corner Code # \_\_\_\_\_

1. Public Land Survey T 7N R 1E \_\_\_\_\_ L-9  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Register of Deeds Stamp & File Number

I, Wendy A. Papineau, in a field survey on June 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

L-9 1/4 Corner Section 24 & 25, T7N-R1E

Wood post placed by R. Thomas, D.S., Jan. 1831  
 S 27 E 10 1/2 lks (6.93') 4" Elm  
 N 27 W 23 lks (15.18') 5" Ash

Survey by I.E. Brands, Surveyor, 1912, recorded in sm. red misc. drain book  
 Monument and references not given

Surveys by M.L. Vanraemdonck, 1995 & 1996 Recorded L. 7 P. 259 and P. 669, S.C.R.  
 Fnd SQ. Bolt  
 South 33.00' R & C #24622  
 North 24.54' Bolt & Tag S.C.S. BM S. Fc Wd Anchor post  
 N 65 E 77.38' Set N & T W. Fc SW Trunk of 4-12" Poplar  
 S 70 E 59.15' Set N & T N. Fc 6" Elm

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

L-9 1/4 Corner Section 24 & 25, T7N-R1E

Fnd 1/2" solid rod with 1" square head per records. This position fits well with I.E. Brands record (C.S. 80.32ch= 5301.12' Meas.= 5309.67') and very closely to a split (West= 2655.36' East= 2654.31'). This position falls 1.43' South of a straight line between section corners.

This position is accepted as the best available evidence of the position of the original corner..

Approved by the Shiawassee County Peer Review Group, Sept. 4, 1997

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

L-9 1/4 Corner Section 24 & 25, T7N-R1E

Replaced 1/2" solid rod with 1" square head with a standard 20" Harrison monument in centerline gravel road, 6" below surface.

South 33.00' 1/2" rod with cap #24622  
 North 24.53' Bolt and S.C.S. BM tag in South face wood anchor post  
 N65E 76.99' Set new nail and tag #39096 in West face on SW trunk of 4-12" Poplar  
 S70E 59.18' Set new nail and tag #39096 in North face of twin 6" Elm

*NCC 10 OCT 97*  
**APPROVED**  
 County Remonumentation  
 Peer Review Group



Signed by Wendy A. Papineau Date Oct. 8, 1997  
 Surveyor's Michigan License No. 41919

**LIBER IR PG 218**