

**SURVEY &
REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

For corners in MAY - 1 1995

94 NOV 16 PM 3:43

Shiawassee COMMISSION located by
(County)

Corner Code #

1. Public Land Survey T 7N R 1E (L-11)
- T _____ R _____
- T _____ R _____
- T _____ R _____
2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____
4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Mark L. VanRaemdonck, in a filed survey on October 21, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the current points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1.) Original: Robinson Thomas D.S. 1831
 Monument: Wood post
 Accessories: Sugar 12 N53°E 36 links
 Do 9 S74°W 18 links
- 2.) R. Kraft: Unrecorded survey Sec. 25 05/22/72
 Monument: Fnd. "T" iron
 Accessories: Prop. corner 33' North Fnd. rerod
 8" Hickory 27' Southwest Fnd. stump
 20" Apple 36.65' Southeast
- 3.) M. VanRaemdonck: Unrecorded survey for Shiawassee County Road Commission 09/26/89
 Monument: Fnd. "T" iron
 Accessories: North 34.11' Set N&T in W. face utl. pole
 N20°W 45.75' Cen. 4" Maple (West face)
 S60°W 40.55' Set N&T in E. face twin 10" Hickory
 N60°W 76.75' Cen. E. face 4" Maple

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original monument and accessories have been obliterated. Found "T" iron as referenced in no. 2 and 3 above. Excavated 8'x8'x2' East of "T" iron at location indicated by proportional measurement. Found no conflicting evidence. Accepted the location of the "T" iron as the best available evidence of the original corner location.

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

Set standard Harrison Marker stamped "REMON 24622" and witnessed by the following accessories:
 North 34.25' Set N&T in E. face utl. pole
 N20°W 102.48' SE corner house foundation
 N60°W 76.80' Set N&T S. face 8" Maple
 S60°W 40.77' Set N&T N. face W. trunk twin 12" Hickory

Signed by Mark L. VanRaemdonck
 Surveyor's Michigan License No. 24622

Date Nov. 9, 1994

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS
 JAN 18, 1971
 REVISED MAY 14, 1971
 REVISED JAN., 1981

REGISTER OF DEEDS
Kaye Shultz
 SHIAWASSEE COUNTY, MICH.
Register of Deeds Stamp & File Number

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

APPROVED
 County Remonumentation
 Peer Review Group
10/18/94 M.L.V.



LIBER 1R PG 88