

**SURVEY &  
REMONUMENTATION**

MAY - 1 1995

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

For corners in

**COMMISSION**

94 NOV 16 PM 3:44

Shlawassee

Located in:

Corner Code #

(County)

REGISTER OF DEEDS

*Larry Smith*  
SHLAWASSEE COUNTY, MICH.

- |                                       |                         |        |
|---------------------------------------|-------------------------|--------|
| 1. Public Land Survey                 | T <u>7N</u> R <u>1E</u> | (L-13) |
|                                       | T _____ R _____         | _____  |
|                                       | T _____ R _____         | _____  |
|                                       | T _____ R _____         | _____  |
| 2. Property Controlling in Section    | S _____ T _____ R _____ | _____  |
|                                       | S _____ T _____ R _____ | _____  |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____ | _____  |
|                                       | S _____ T _____ R _____ | _____  |
| 4. Lot No. _____, Recorded Plat _____ |                         |        |
| 5. Private Claims _____               |                         |        |

**Register of Deeds Stamp & File Number**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Mark L. VanRaemdonck, in a filed survey on October 21, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the current points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

Original: Robert Clark Jr., D.S. 1831  
 Monument: Wood post  
 Accessories: Maple 8 N67½°E 12 links  
 do 10 N80°W 26 links

**APPROVED**

County Remonumentation  
Peer Review Group  
10/18/94 M.L.V.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Original monument and accessories have been obliterated. Re-established the location of the South ¼ corner of Section 36, T7N-R1E using the single proportion method. This location is at the centerline of the asphalt surface of Hibbard Road, and in line with an old fence line running North. This location is accepted as the careful and faithful re-establishment of the original corner location. Excavation for Harrison marker installation provided no further evidence.

**C. Description of monument for corner and accessories to perpetuate locating the position of the corner:**

Set standard Harrison marker stamped "REMON 24622" and witnessed by the following accessories:  
 N25°W 36.63' Set N&T Southwest face 24" Maple  
 S25°W 39.47' Set N&T East face 24" Maple  
 N60°E 62.36' Set N&T South face 18" Hickory  
 S70°E 62.00' Top center West end 12" concrete culv.



Signed by *Mark L. VanRaemdonck*

Date Nov. 9, 1994

Surveyor's Michigan License No. 24622

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS JAN 18, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983