

SURVEY & REMONUMENTATION

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

For corners of **COMMISSION**

94 NOV 16 PM 3:41

Shiawassee Located in: Corner Code #
 (County)

1. Public Land Survey T 7N R 2E (K-11)
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

REGISTER OF DEEDS
Raye A. Smith
 SHIAWASSEE COUNTY, MICH.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Mark L. VanRaemdonck, in a field survey on October 21, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the current points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Original: William Brookfield, D.S.
 Monument: Wood post
 Accessories: S. Maple 14 N83°E 5
 do 14 N74°W
- O.M. Elliot: Book 24, page 75. 1956.
 Monument: Not given
 Accessories: Consumer's sign post SE 32.5'
 Walnut 12" SW 72.1'
 Iron sign post NE 41.85'
- C.F. Smith: M.D.O.T. Dec. 1965.
 Monument: ½" iron cen. Morrice Road
 Accessories: T. pole N45°W 35.67'
 T. pole S36°E 56.49'
 Road sign N60°E 44.80'
- J. Quine: L.C.R.C. recorded Liber 1, page 298. 2/9/73.
 Same as no. 3 above.
- M. VanRaemdonck: Survey recorded Liber 3, page 361. 3/21/80.
 Monument: Found ½" pipe
 Accessories: Same as no. 3 above.
- J. Matonich: L.C.R.C. Liber 2, page 546. 4/22/88.
 Monument: ½" pipe
 Accessories: N60°E 44.8' Road sign
 S60°E 53.9' N/disk NW face P.P.
 N70°W 51.06' N/disk SE face P.P.
 N80°W 22.15' S. edge S. leg sign post

APPROVED
 County Remonumentation
 Peer Review Group
 9/27/94 M.L.V

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original monument and accessories have been obliterated. Found ½" pipe as referenced in no. 2, 3, 4, 5 and 6 above. Accepted this location as the best available evidence of the original corner location. Found a R.R. spike 0.15' East and 0.20' North of ½" pipe 0.3' below surface while excavating for installation of Harrison marker.

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

Set standard Harrison marker stamped "REMON 24622" and witnessed by the following accessories:
 S65°E 53.94' Found N&T NW face utl. pole
 N75°E 47.94' S. edge stop sign post
 N30°W 81.13' Set N&T E. face 6" Maple
 N80°W 51.30' Set N&T S. face utl. pole
 West 10.00' W. edge asphalt surface



Signed by Mark L. VanRaemdonck
 Surveyor's Michigan License No. 24622

Date Nov. 10, 1994

LIBER 1R PG 74