

**SURVEY &
REMONUMENTATION**

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

For corners in

COMMISSION

94 NOV 16 PM 3:41

Shiawassee _____ Located in: _____ Corner Code # _____
(County)

1. Public Land Survey T 7N R 2E (L-11)
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No. _____ Recorded Plat _____

5. Private Claims _____

REGISTER OF DEEDS
Kaye Smith
SHIAWASSEE COUNTY, MICH.
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Mark L. VanRaemdonck, in a field survey on October 21, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the current points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1.) Original: William Brookfield. 1824.
Monument: Wood post
Accessories: W. Oak 24 N45°E 23
W. Oak 8 S59½°E 83
- 2.) E. F. Joslin, County Surveyor. 1905.
Monument: 5/8" iron rod
Accessories: W. Oak 7" N2°W 35 links
Butternut 4" S25½°W 52 links
Cherry 7" S39°W 55 links
- 3.) E. S. Brewer: L.C.R.C. recorded Liber 2, page 194. 8/1/79.
Monument: R.R. spike
Accessories: Cen. tele. pole & box S33½°E 29.6'
Cen. 10" Oak anchor post S70 3/4°E 86.0'
Cen. 14" Cedar in yard S24°W 88.8'
Cen. 18" Apple tree N63°E 77.5'
- 4.) John D. Matonich: L.C.R.C. Liber 2, page 548. 4/22/88.
Monument: Found iron
Accessories: SW 88.4' 12" Cedar
North 16.33' R.E.I. Iron
S60°W 35.40' Mail box #451
S45°E 29.37' N&F SE face P.P.
N50°E 77.32' N&F SE face 16" Apple

(continued on reverse side of this sheet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original monument and accessories have been obliterated. E. F. Joslin's monument and accessories have been obliterated. Found R.R. spike as referenced in no. 3, 4 and 5 above. Found no conflicting evidence and accepted this location as the best available evidence of the original corner location. Excavation for installation of Harrison marker provided no further evidence.

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

Set standard Harrison marker stamped "REMON 24622" and witnessed by the following accessories:
S50°W 102.02' Set N&T in NW face 12" Pine
S20°W 88.63' Set N&T in E. face 18" Cedar
S40°E 29.44' Set N&T in NE face utl. pole
S70°E 88.89' R&C #24622 @ 33' R/W line
N70°E 77.63' Set N&T in NW face 18" Apple

APPROVED
County Remonumentation
Peer Review Group
9/27/94 M.L.V.



Signed by Mark L. VanRaemdonck
Surveyor's Michigan License No. 24622

Date NOV. 10, 1994

LIBER 1R **PG** 77

A. Description of original monument and accessories and/or subsequent restoration:

(continued from front)

5.) M. L. VanRaemdonck: Survey recorded Liber 6, page 806. 6/10/92.

Monument: R.R. spike

Accessories: SW 88.40' 12" Cedar

North 16.33' R.E.I. iron

S60°W 35.40' Mail box #451

S45°E 29.37' N&F SE face P.P.

N50°E 77.32' N&F SE face 16" Apple

S45°E 29.15' NW face U/P

S15°W 88.65' Cen. 15" Red Cedar

North 1.5' Phys. centerline

N60°E 77.80' Cen. 20" Apple