

**SURVEY &
REMONUMENTATION**

MAY - 1 1995

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

94 NOV 16 PM 3:41

For corners in **COMMISSION**

<u>Shiawassee</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>7N</u> R <u>2E</u>	<u>(L-13)</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

REGISTER OF DEEDS
Kayle Brudner
SHIAWASSEE COUNTY, MICH.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		6		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Mark L. VanRaemdonck, in a field survey on October 21, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the current points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1.) Original: Joseph Wampler, D.S. 1824
Monument: Wood post
Accessories: Lynn 10 N42½°W 20 links
Dogwood 9 S26°W 25 links
- 2.) Ezra Mason, County Surveyor. May 1865.
Monument: Not given
Accessories: Elm 14 S66°W 121 2/3

APPROVED

County Remonumentation
Peer Review Group
9/27/94 M.L.V.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original monument and accessories have been obliterated. County Surveyor's monument and accessories have been obliterated. I re-established this location using measurements proportional to those shown in County Surveyor's records along the South line of Section 36 and the North and South ¼ line. This location matches 1/8 line fence in Southeast ¼ and is at the split of the distance between corners K-13 and M-13. This location is accepted as the careful and faithful re-establishment of the corner location based on the best available evidence.

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

Set standard Harrison marker stamped "REMON 24622" and witnessed by the following accessories:
N40°W 30.13' Set N&T S. face utl. pole
S10°W 27.29' Set N&T E. face 14" Poplar
S70°E 68.24' Set N&T W. face 36" Hickory
N60°E 49.07' Set N&T S. face 12" Box Elder



Signed by Mark L. VanRaemdonck

Date Nov. 10, 1994

Surveyor's Michigan License No. 24622

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS JAN 18, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

LIBER 1B **PG** 79