

**SURVEY &
REMONUMENTATION**

MAY - 1 1995

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

For corners in **COMMISSION**

94 NOV 16 PM 3:44

<u>Shiawassee</u>	Located in:	Corner Code #
(County)		
1. Public Land Survey	T <u>7N</u> R <u>3E</u>	<u>(L-11)</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____	Recorded Plat _____	
5. Private Claims _____		

REGISTER OF DEEDS
Hayes
SHIAWASSEE COUNTY, MICH.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Mark L. VanRaemdonck, in a filed survey on October 21, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the current points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1.) Original: Joseph Wampler, D.S. 1822
Monument: Wood post
Accessories: W. Oak 10" N68°E 15
Elm 7" S66½°W 5
- 2.) Survey by Monroe Holley, 1853, of Section 25, T7N-R3E, Gives no monument or accessories.
- 3.) Survey by Monroe Holley, 1854, of Section 36, T7N-R3E. Gives no monument or accessories.
- 4.) Survey by Ezra Mason, Section 25, T7N-R3E. Gives no monument or accessories.
- 5.) Survey by Ezra L. Mason, Section 36, T7N-R3E. Gives no monument or accessories.
- 6.) Survey by E. F. Joslin, CR Book 17, page 130, Section 25, T7N-R3E. Gives no monument or accessories.
- 7.) M. VanRaemdonck: Survey recorded Liber 6, page 247.
Monument: Rerod and cap #24622
Accessories: North 8.07' Set N&T E. face S. trunk 24" twin Oak
S65°E 7.53' Set N&T in S. face 4" W. Oak
East 20.16' Set N&T in S. face 10" Ash
S40°E 32.65' Set N&T in W. face 10" Cottonwood
- 8.) E. S. Brewer: Survey recorded Liber 6, page 588.
Monument and accessories same as no. 7 above.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original monument and accessories have been obliterated. Calculated the distance between South ¼ corner Section 36 to occupied center of Section 25. Equals 8153.21 feet. Distance shown in survey by Mason in Section 36 (5574.36) and Holley in Section 25 (2585.58) equals 8156.94. Located point on North and South ¼ line fence at Holley's distance from center on Section 25 at this location, I found a 5" x 8" x 5" stone. This stone is 2627.12 feet East of the Northwest corner of Section 36. Holley's survey gives this distance as 2628.78 feet. I accepted the location of this stone as the careful and faithful perpetuation of the original corner location.

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

Set standard Harrison marker stamped "REMON 24622" and witnessed by the following accessories:
N60°W 4.69' Set N&T S. face 24" Oak
N20°W 7.55' Set N&T e. face 18" Oak
N70°E 8.15' Set N&T S. face 12" Elm
S40°E 13.51' Set N&T NE face 14" Elm
S60°W 13.42' Set N&T E. face 8" Elm

APPROVED
County Remonumentation
Peer Review Group
10/18/94 M.L.V.



Signed by Mark L. VanRaemdonck

Date Nov. 9, 1994

Surveyor's Michigan License No. 24622