200 27 200

SECTION

## 1999 REMONUMENTATION PROGRAM

## LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For o	come	rs	in
-------	------	----	----

Marine Provided	6-1-	 DEMAN

3026095 Page: 1 of 2 10/05/1999 02:19P

			Kaye Grubba - Shiawassee Co. REMON L-1 P-288										
Shiaw (Count			Locate: Caledo	d In: nia Twp	Corner Code #								
	ic Land Survey	0	T <u>7N</u> T	R <u>3E</u> R	APPRO	Regist	er ol	Dee:	ds Stan	np & File	• Numb	er	
	erty Controlling	S	Ţ	R R		VED							
3. Misc	ellaneous perty in Sec.	s s s	Ť T	R R	APPRO COUNTY Remo	onumentation Group of	1 A	. <u>в</u>	C D	E F	<u>эн</u> _	I J K	L M
4. Lot No, Recorded Plat 5. Private Claims			County Rev	onumentation Group of	2	6	5	4	3	2	1		
	belegge December	D.C	: <b>G</b> -1	4		1999	4	7	8	9	10	11	12
I, <u>John H. Rauser, P.S.</u> , in a field survey on <u>September</u> 1999.  do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as				5 6 7	18	17	16	15	14	13			
				8	19	20	21	22	23	24			
	f Law; establishe ed below:	a, re-es	(abiisned,	monumen	ted, re-montaneated,		10	30	29	28	27	26	25
NOTE:	Not more than a on this certifica		s, all in tl	he same t	own and range, may	be recorded	11   12   13	31	32	33	34	35	36
A. D <u>M-7</u>	Section Corner 1822 Wood past 1874 County Sur 1/4 E 2 1877 County sur	common placed to rvey reco 2 lks, not vey reco distance	n to Secs by J. Wan ord by L. I led the ck and by L. M as in 187	s. 13&24, npler, D.S Mason, C. osing dista Mason, C. 74 record	ccessories and/or T7N-R3E, Caledonia ., Ash 7" N2W 22.5 lk S., Shia. Co. Survey ance of A-7, T7N-R4E S., Shia. Co. Survey I	i <u>Township, Shiawa:</u> s; Ash 11" S9E 19.5 Records, 1874-1883; Eas 100lks (66'), Mea Records, 1874-1883,	ssee Iks witn sure Mea	essed d dist	d by Ein tance to I to M-6	M-8 4U	12 ch (a	2647.92	γ,

1950 MSHD construction plans, State Highway Plan L-72-A2, State Project 76-17, Fed. Proj. F-54(5), called for 3/4" pipe 22.51 feet North of station 288+88.77, witnesses 12" elm N37W, 35.66'; 15" ash N25W, 46.82'; 14" oak N35E, 51.85'; 12" oak N19E, 78.76'

1958 County Survey by O.M. Elliot C.S., CR 26, P.56, survey in Sec. 19, T7N-R4E, witnessed A-7: 22.5' N of centerline M-21; 12" Elm N37W, 35.66'; 15" Ash N25W, 46.82'; 14" Oak N35E, 51.85'

Part A, continued on back:

## B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Section Corner common to Secs. 13&24, T7N-R3E, Caledonia Township, Shiawassee County

Found railroad spike in monument box North side of State Highway M-21(22.3' North of the physical centerline) in the approximate centerline of Geeck Road. Found and verified witnesses from the 1965 to the present. Found no conflicting evidence in the vicinity of this corner. Record states A-7, T7N-R4E is 1 chain (66') South, but found no evidence of this position. Found ½" pipe raised with ½" rerod, 1304.74' South and 3.8' West of a line between M-7 and M-8. The distance to L-7 checks with record measurements. We recommend that the found railroad spike the monument box be accepted as the best available evidence of the position of the original government corner and be replaced with a standard Shiawassee County Harrison monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-7 Section Corner common to Secs. 13&24, T7N-R3E, Catedonia Township, Shiawassee County

Set a standard 20" Harrison monument in an existing monument box at the position approved by the Shiawassee Count Peer review Group.

48.54 Fnd 1/2" rod w/cap #24622 N43°W S36°W 90.22' Fnd N/T E fc PP Chisled "x" top center S-end new 12" CMP N16°W 83.74 113.73' PK/flag SE fc PP N72°E E-edge road sign post N40°W 46.96" N80°E 50.261 NE corner E-end conc curb M-21م S01°W 22,30

my / oly / . Kause

sy

JOHN H.
RAUSER
PROPESSIONAL
SURVEYOR
NO.
SOME

AN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971 REVISED MAY 14, 1976 REVISED JAN., 1913 ADAPTED FOR WORD PROCESSING MARCH, 1933

Signed by \_

Surveyor's Michigan License No.

39096



Page: 2 of 2 10/05/1999 02:199 L-1 P-288

## Part A. continued :

- 1965 Certificate of Survey by J.F. Quine, #10704, set R/R spike reestablished from ref. as shown on MSHD constr. plans. Remaining refs. Oak, 14" N35E 51.85'; Oak 12" N19E 78.76'; 22.51' N. of CL. M-21, New refs. Iron pipe fnc cor NE46', iron pipe rd sign post NW 39.9'; NW 26.5' NE cor conc CB; M = to M-8 2648.0 1974 Rowe witness card NE 46' iron fence post, NW 39.9' road sign, NW 26.5' NE cor conc CB
- 1985 Act 132 by J.N. Owens, P.S. #20709, L.4, P. 327-328, Found R/R spike witnessed by NE 46.4' iron fence post; NW 39.9' road sign; NW 26.5' NE cor conc CB
- 1988 Act 132 by J.D. Matonich, P.S.#31598, L. 5, P.115, found R/R spike in mon box, witnessed by N35E 46.51' PK/flag in SE fce 4" wood fence post; N40W 47.17' East edge road sign post; N80E 50.37' NE cor E. end conc.curb; S35W 90.25' N&T SE fce P/P; North 2.27 found PK nail
- 1988 Rowe witness card: East 1.87' fnd pk nail, West 1.92' fnd pk nail, South 2.38' fnd pk nail
- 1989 Act 132 un-recorded by M.L. Vanraemdonck, P.S. #24622, fnd R/R spike in mon box, same witnesses as 1988 record, measured to L-7 2591.03' and to M-6 2635.38'.
- 1989 Act 132 by N.C. Caldwell, P.S. #12018, L. 5, P. 267 SCR, found r/r spike in mon box, used same wits as 1988, L. 5, P.115
- 1996 Act 132's by J.H. Rauser, P.S. # 39096, L. 7, P. 588 & 600, fnd R/R spike in mon box, N72E 113.76' PK w/tag in SE fce P/P; N16W Set chis "+" t/c S end 12" conc culv.; S36W 90.16' N&T E fce P/P; North 2.24' PK nail; South 2.38' PK nail; N43W 48.58' 1/2" rod w/cap #11192

SURVEY & RENOVUMENTATION

----

SECTION