

SURVEY &
REMONUMENTATION

NOV 03 1998

A. Continued:

1897 County Survey Record Book G, P. 130 by E.F. Joslin; flat iron bar at corner.
Hickory 9" S70.5E 32.75 lks (21.62')
Hickory 7" S32E 63.25 lks (41.75')
Also Book B1, P. 115 lists W. Oak 3" S85W 35.5 lks

1964 County Survey Record Book 6, P. 33 by J.F. Quine, fnd good dip needle reaction-did not dig up. Noted: "Joslin's stake"
N45.5W 88.9' SE cor fndtn frame barn
N88W 91.2' 30" Oak in fenceline
S71.5E 25.4' 15" Hickory (S70.5E Joslin BT)
S34.67E 44.2' 18" Hickory (S32E Joslin BT)
in line with fence lines E-W

1966 J.F. Quine fnd plowpoint 3" deep brick and crockery around it.

1972 Act132 by J.F. Quine L. 1, P. 330; no witnesses given.

1972 County Survey Record Book 17, P. 9; "Geeck Rd had been regraded & bearing trees gone, except Oak to West still standing.
Plowpoint & stone & crockery ok 2" deep.
N45.5W 88.9' SE cor. fndtn of frame barn
West 91.2' 30" Oak in fenceline
S54W 33.4' Center, N end, 12" CP field entrance culvert
N85W 24.0' Center S end
N45W 35.5' Center, N end, 12" CP field entrance culvert
S40W 53.3' Center, S end
S23W 101.0' P/P
S17E 111.5' Brace pole, power line
South 2639.55' 1/4 Post

1975 Act 74 by J.F. Quine, L. 1, P. 459; listed witnesses from 1972 county record.

1990 Act 132 by N.C. Caldwell, L. 5, P. 958-960; fnd 1/2" bar per corner record L. 1, P. 439 & survey record L. 1, P. 330.
N51W 89.23' SE corner of barn conc fndtn
East 49.07' Nail & tag in N Fce P/P
N87W 90.70' Nail & tag in S Fce 36" Oak
S20W 101.00' Nail & tag in NW Fce P/P
West 50.12' 1/2" bar with cap #10704

1995 Act 132 by J.H. Rauser, L. 7, P. 408-410; fnd 1/2" rod 4" below grade. Measured 2639.31' to M-10.
East 49.04' Fnd N&C #12018 N Fce P/P
S20W 100.82' Fnd N&C #12018 NE Fce P/P
West 24.08' T/C 12" conc culv (S end)
N45W 89.19' SE cor barn fndtn



3007726
Page: 2 of 2
10/27/1998 03:22p