

SURVEY & REMONUMENTATION

MAY - 1 1995

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

94 NOV 16 PM 3:44

For corners in

COMMISSION

Shiawassee Located in: Corner Code #
 (County)

1. Public Land Survey T 7N R 3E (M-11)
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____ Recorded Plat _____

5. Private Claims _____

REGISTER OF DEEDS
Kaye Shultz
 SHIAWASSEE COUNTY, MICH.
Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Mark L. VanRaemdonck, in a filed survey on October 21, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the current points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- Original: Joseph Wampler, D.S.
 Monument: Wood post
 Accessories: Alder 3 N1°E 6
 Lynn 2 S5°E 5½
- E. F. Joslin: Book B-1, page 115. 08/16/1897
 Monument: Granite boulder
 Accessories: Granite boulder 29" N03°E 15 links
- E. S. Brewer: L.C.R.C. Liber 2, page 448, 09/20/86.
 Monument: R.R. spike
 Accessories: N61½°E 57.75' Old wood anchor post
 S48½°E 79.5' Face of NW Power pole of H-frame line
 S37½°E 30.30' Cen. tele. box
 S09°W 15.30' E. leg of arrow road sign
 N51°W 47.75' Geeck, Lytle Road sign post
 N22°W 56.25' Cen. tele. box



(Reference 1854 survey of Southwest fractional ¼ Section 30, T7N-R4E, by Monroe Holley, Book A, page 117, Book B, page 56) South ¼ corner Section 30 3641.00 East. West ¼ corner Section 30 2649.90' North)

- M. VanRaemdonck: Survey recorded Liber 6, page 247. July 31, 1992.
 Monument: R.R. spike
 Accessories: N61.5°E 54.75' Old wood anchor post
 S37.25°E 30.30' Cen. tele. box
 S09°W 15.30' E. leg arrow sign
 N51°W 47.78' Geeck, Lytle Road sign post
 N22°W 56.25' Cen. tele. box

APPROVED
 County Remonumentation
 Peer Review Group
 9/27/94 M.L.V.

Found R.R. spike 08/24/94.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Original monument and accessories have been obliterated. E. F. Joslin's monument and accessories have been obliterated. Found R.R. spike as referenced in no.'s 3 and 4 above. This is a common corner with T7N-R4E as per G.L.O. notes. Accepted this location as the faithful re-establishment of the corner location. Excavation for Harrison marker provided no further evidence.

C. Description of monument for corner and accessories to perpetuate locating the position of the corner:

Set standard Harrison marker stamped "REMON 24622" and witnessed by the following accessories:
 S60°E 79.90' Set N&T in NW face utl. pole
 S10°W 18.62' Top cen. E. end 12" conc. culv.
 S50°W 31.63' Top cen. W. end 12" conc. culv.
 N25°W 46.65' Set rerod & cap #24622

Signed by Mark L. VanRaemdonck Date Nov. 9, 1994

Surveyor's Michigan License No. 24622

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS JAN 18, 1971
 REVISED MAY 14, 1975
 REVISED JAN., 1983

LIBER 18 PG 100