

**SURVEY &  
REMONUMENTATION**

MAY - 1 1995

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

RECORDED

For corners in

**COMMISSION**

94 NOV 16 PM 3:45

Shiawassee Located in: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)

- |                                    |   |           |   |           |        |
|------------------------------------|---|-----------|---|-----------|--------|
| 1. Public Land Survey              | T | <u>7N</u> | R | <u>3E</u> | (M-12) |
|                                    | T | _____     | R | _____     | _____  |
|                                    | T | _____     | R | _____     | _____  |
|                                    | T | _____     | R | _____     | _____  |
| 2. Property Controlling in Section | S | T         | R | _____     | _____  |
|                                    | S | T         | R | _____     | _____  |
| 3. Miscellaneous Property in Sec.  | S | T         | R | _____     | _____  |
|                                    | S | T         | R | _____     | _____  |
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

REGISTER OF DEEDS  
*Kaye Shultz*  
SHIAWASSEE COUNTY, MICH.

**Register of Deeds Stamp & File Number**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Mark L. VanRaemdonck, in a filed survey on October 21, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the current points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1.) Original: Joseph Wampler, D.S.  
Monument: Wood post  
Accessories: Hickory 5 N4°E 14½  
Hickory 9 S10°W 26
- 2.) Monroe Holley, Deputy County Surveyor. Book A, page 113. 03/28/1854  
Monument: Not given  
Accessories: W. Oak 10" S48°E 36  
Cherry 11" S44°W 31
- 3.) Ezra Mason, County Surveyor. Book A, page 159. Book B, page 91. 01/02/1861  
Monument: Not given  
Accessories: W. Oak 10" S57 3/4°E 39½  
W. Oak 10" S13 3/4°E 40

**APPROVED**

County Remonumentation  
Peer Review Group  
9/27/94 M.L.V.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Original monument and accessories have been obliterated. Accessories from Holley and mason surveys have been obliterated. The location of the East and West ¼ line fence in the Southeast ¼ of Section 36 fit well with Mason's 1861 survey. Based on proportional measurements from Mason's survey along the East and West ¼ line I re-established the corner location. Excavation revealed no evidence. There is a row of large boulders and rocks running South from this location. This location if accepted as the careful and faithful re-establishment of the original corner location based on the best available evidence.

**C. Description of monument for corner and accessories to perpetuate locating the position of the corner:**

Set standard Harrison marker stamped "REMON 24622" and witnessed by the following accessories:  
S80°E 12.73' Set N&T in North face 15" Red Oak  
N80°W 10.21' Set N&T in South face 12" Red Oak  
S35°W 36.10' Set N&T in East face 6" Linden  
South 26.24' Set N&T in West face 4" Hackberry



Signed by *Mark L. VanRaemdonck*

Date Nov. 9, 1994

Surveyor's Michigan License No. 24622

**LIBER** IR **PG** 101