

**SURVEY &
REMONUMENTATION**

SEP 29 1994

COMMISSION

For corners in

Shiawassee
(County)

Located In:

Corner Code **##**

- | | | | | | |
|------------------------------------|---|-----------|---|-----------|-------------|
| 1. Public Land Survey | T | <u>7N</u> | R | <u>4E</u> | <u>K-13</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

RECORDED

91 SEP -6 AM 11:04

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER OF DEEDS

Kaye Hunter
SHIAWASSEE COUNTY, MICH.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Norman C. Caldwell, in a field survey on July, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-13 Sec. cor., 35 & 36, T7N-R4E

Wood post placed by J. Wampler, 1822
S34°E 13 lks. (8.58') 7" Beech
N49°W 22 lks. (54.12') 6" Beech

Survey by E.S. Brewer, 1973, recorded in L. 1,
pgs. 598 of surveys.
Mon. & Refs. Not Given

Survey by E. Mason, Co. Surveyor, 1866,
recorded in Co. Surveyors records pgs.
60-61.
Mon. & Refs. Not Given

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-13 Sec. cor., 35 & 36, T7N-R4E

Set std. 20" Harrison Marker, 12" below ground, by reconstructing E.S. Brewer's survey L. 1, pgs. 598-599, as approved by the Shiawassee County Remon. Peer Review Group and is accepted as the best available evidence of the position of the original corner. Cor. falls in middle of a cultivated field.

APPROVED
County Remonumentation
Peer Review Group
8/16/94 MLV

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13. Sec. cor., 35 & 36, T7N-R4E

Set std. 20" Harrison Marker, 12" below ground, by reconstructing E.S. Brewer's survey L. 1, pgs. 598-599, as approved by the Shiawassee County Remon. Peer Review Group and is accepted as the best available evidence of the position of the original corner. Cor. falls in middle of a cultivated field.

- S88°35'51"W 348.58' Fnd. 3/4" I.D. pipe 18" B.G. at Sec. cor. 1 & 2, T6N-R4E, (R)
- S57°45'W 411.62' Set N & T #12018 SE fc. 30" Basswood
- S57°34'E 390.69' Set N & T #12018 W. fc. 14" Elm
- N88°35'51"E 311.60' Fnd. pipe - Brewer (R)
- N54°51'E 409.69' Set N & T #12018 S. fc. 20" Elm



Signed by *Norman C. Caldwell*
Surveyor's Michigan License No. 12018

Date 10 AUG 94