

SURVEY &
REMONUMENTATION

NOV 03 1998

A. Continued

SECTION

- 1946 County Survey by F.A. Gould: Fnd a 3/4" bolt 1ft long inside of an upright tile with stone & pieces of conc. around, also a black s
persisted going down at least 18" thru old road & directly below bolt had nut & washer on it . Replaced with well point placed 3" be
surface with pieces of stone, tile & conc. around and witnessed to center of all: Elm 24" S48W, 51.0', W. Oak 12" South, 27.30', W. O
20" S25E, 30.90'. CR 39, page 28-33
- 1949 Don Bingham of Flint measured 2644.20' to M-9.
- 1952 Plat of Woodland ties point of beginning to L-9; N87°43E, 495.54' from S1/4 of Sec. 24; F.A. Gould surveyor
- 1958 County Survey by O.M. Elliot used Mason's 1866 survey of Sec 25, Elliot listed 1866 witnesses to L-9; CR 28, P. 42
- 1963 Drain Record by O.M. Elliot Large bolt 14" below tar pvmt.; P/P N50W, 42', Maple 14" N50E 66', Oak 24", S20E, 31'
- 1963 Survey & Drain Rec. by J.F. Quine; Fnd iron stake 12" deep, brought to surface with 1"□ head bolt,
(Old BT) S63W 50.8', 15" Oak S03'W, 27.3', Tele. Pole N55°15'W, 42.4', Wood post N01°15'E, 25.6', 12" Maple N70°30'W
65.6', (old BT) 28" Elm, S63W, 50.8', South 2' from centerline Lennon Rd.
- 1963 CPCO survey by J.L. Halfacre witnessed found 1" square bar, in line with fences N&S; Job 6180, Dwg S-F16602
18" Oak South 27.35'
Tel Pole NW 42.38'
14" Maple NE 65.44'
26" Oak SE 30.19'
- 1972 Act 132 by K.R. Piotrowski, Found Bolt; T/P N55W, 42.10', 16" Oak South, 26.75', 28" Oak S25E, 29.85'
- 1972 CPCO survey by E. McCombs, Found 3/4" pipe brought to surface with R/R spike; 16" Oak South, 27.25', 28" Oak S25E, 31.0E
16" Oak North, 43.0', 14" Maple N60E, 65.75', Job 8757, file 3563, Dwg S-F 17562, Sheet 21, Rev C
- 1973 Act 132 by E.S. Brewer L. 1, P. 391, corner shown on survey. No witnesses.
- 1975 Act 74 by G.R. Stonerock L. 1, P. 632; Fnd 1/2" iron in Lennon Rd.
N30W 42.22' N&C in T/P
S25E 29.74' N&C in 28" Oak
South 26.69' N&C in 15" Oak
- 1975 Act 74 by J.F. Quine L. 1, P. 494; Fnd rusty 1 1/2" iron pipe stake 12" deep & set 1" square head iron bolt directly over 1 1/2" pipe.
N55.25W 42.4' T/P
N01.25E 25.6' Wooden corner fence post
N70.5'E 65.6' 12" Maple
S03W 27.3' 15" Oak (used for fence corner)
S63.25W 50.8' 28" Dead Elm
North 2.0' CL of Lennon Rd sealcoat pavement
- 1976 Act 132 by J.S. Fokens L. 2, P. 325-326 SCR
- 1977 Act 132 by A.F. Miller L. 2, P. 627; Fnd rerod 2' South of centerline.
N50W 42.25' N&T in T/P
North 42.95' N&T in 20" Oak
South 26.76' N&T in 18" Oak
S10E 29.80' N&T in 30" Oak
- 1977 Act 74 by E.J. McCombs L. 1, P. 73; Fnd 3/4" pipe on line fence to North.
South 27.25' 16" Oak
S35E 31.08' 28" Oak
North 43.00' 16" Oak
N60E 65.75' 14" Maple
- 1978 Act 132 by J.S. Fokens L. 3, P. 44 SCR; Fnd 1/2" re-rod; S85E 42.94' N&F in 15"Oak, S75W, 29.79' N&T 26"Oak, West 26.72'
N&T 14" Oak
- 1982 Survey Sketch by M.L. Vanraemdonck, Fnd R/R spike and L-9 no wits listed
- 1986 Act 132 by J.D. Matonich, L. 4, P.444 SCR, Fnd R/R spike 2.5' South of centerline;
S45E 31.04' Set nail in W. fce 28" Oak
S45E 30.69' fnd over grown nail in E. fce 28" Oak
South 27.99' Set nail in W. fce 20" Oak
N55W 42.44' fnd nail and tag in SW fce T/P
N55W 42.22' fnd nail and tag in SE fce T/P
- 1987 Act 132 by M.L. Vanraemdonck, L4, P.666-667 SCR; Fnd R/R spike 2.5' south of centerline, listed same wits as 1986 survey
- 1989 Act 74 by N.C. Caldwell L. 2, P. 655; Fnd R/R spike 2.5' S of CL of pavement, same witnesses as 1986 Act 132 by J.D. Matonic
- 1992 Act 132 by M.L. Vanraemdonck, Fnd R/R spike 2.5' South of centerline of pavement.
S45E 31.04' Nail W Fce 28" Oak
S45E 30.69' Overgrown nail in E Fce 28" Oak
South 27.99' Nail W. Fce 20" Oak
N55W 42.44' N&D in SW Fce T/P
N55W 42.22' N&D in SE Fce T/P
- 1992 Act 132 by C.H. Carlson, unrecorded, Fnd re-rod. 2' south of centerline, N50W 42.25' N&T in T/P, North 42.95' N&T in 20"Oak,
South 36.72' N&T in 18" Oak, S10E 29.80' N&T in 30" Oak
- 1993 Act 132 by M.L. Vanraemdonck, L4, P.666-667 SCR; Fnd R/R spike 2.5' south of centerline; wits same as 1986 survey
- 1996 Act 132 by M.L. Vanraemdonck, L4, P.666-667 SCR; Fnd R/R spike 2.5' south of centerline; wits same as 1986 survey
- Undated Act 132 by B. Griggs; Fnd iron, North 42.33' Nail 15" Oak
N60W 42.00' Nail T/P
N60E 65.43' Nail 12" Maple
S20E 29.86' Nail 30" Oak



3007721
Page: 2 of 2
10/27/1998 03:22P